

1-
2-

Clinton County Remonumentation
North 1/4 Corner Section 6, T. 5N.-R. 1W., Bath Township
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIDER 004 PAGE 272

For corners in

Clinton Located In: Corner Code #
 (County)

1. Public Land Survey T 5N R 1W B-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECORDED

Dec 28 3 33 PM '98

REGISTER OF DEEDS
 CLINTON COUNTY, MICH.
Carole Winkley

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Samuel J. Clark, in a field survey on July 23, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		●											
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-1 North 1/4 Corner Section 6, Bath Twp.

Corner not set in original survey of Section 6

Survey of Section 6 by R.H. Colburn, December 10, 1883 and following days, "Established Quarter Post in compliance with the statute", witnesses: S15°E, 32 1/2 lks. 18" Elm
 S70°45'W, 38 1/2 lks. 18" W. Elm

(Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 North 1/4 Corner Section 6, Bath Twp.

This position not established by original government surveyors. Found 1/2" Rerod (no cap) at North edge base of rotted and broken off fence post 2.46' North of Township line. Found 14" Maple, no nail and tag, N36°W at 7.29'. Position checks favorably in an East-West direction with the resurvey by R. H. Colburn of Section 6, Bath Twp. and is accepted as the best available evidence of the position of the corner. Removed rerod found, rocks, and stub of old fence post and remonumented corner 2.46' south of position of 1/2" Rerod, on Township line, with *Standard Clinton County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 North 1/4 Corner Section 6, Bath Twp.

*Set Standard Clinton County Monument

Set Nail & Tag #41096	Southwest Face 36" Elm	North 72° West	48.14'
Set Nail & Tag #41096	East Face 24" Twin Maple	North 10° West	52.32'
Set Nail & Tag #41096	West Face 20" Oak	North 29° East	48.84'
Set Nail & Tag #41096	West Face 18" Maple	South	33.39'

*Standard Clinton County Monument at B-13, Bath Township, S.89°57'08"E. 187.92'

*Standard Clinton County Monument at A-1, Bath Township, N.89°57'08"W. 2805.35'

*Standard Clinton County Monument being a 2 1/2" Diameter Steel Tube, 30" long, with a stamped brass cap, restamped #41096, and breakaway magnetic base.

Signed by Samuel J. Clark
 Surveyor's Michigan License No. 41096

Date 12/23/98



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED, MAY 14, 1975
 REVISED JAN, 1981
 REVISED OCT, 1995

APPROVED BY
 CLINTON COUNTY PEER GROUP
 DATED 11/17/98
SJC

- ◆ Certificate of Survey, G. Fauser, # 16089, January, 1973,
1/2" Rebar and Cap set at Fence Post - fence going east-west, south
10" Ash N10°W 18.14'
24" Oak S87°E 28.34'
10" Ash S12°E 31.05'
26" Ash S45°W 57.07'

- ◆ Recorded Survey, L. Bryan, #25832, March 5, 1984, Liber 4, Pg. 130,
Found 1/2" Bar and Cap at base of corner post, Consumers Power Company #18657,
fences south, east and west
Found "pk" nail north side 20" Oak S85°E 28.73'
Found "pk" nail north side 24" Basswood S45°E 56.80'
Set nail and Tag northeast side 10" Maple N45°W 7.25'

SURVEY & RECONSTRUCTION

FEB 18 1999

SECTION