

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Clinton

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5N R 1W G-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

MAR 15 3 38 PM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 20

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5			4		3		2			
3													
4	7		8			9		10		11		12	
5													
6	13		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

Dwight R. Schofield

I, Dwight R. Schofield, in a field survey on December 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey done in November of 1826 by Harvey Parke
Subsequent restoration recorded 3/23/92 in Liber 2, Page 828

- 1" square bar
- S 45° E NE side of 34" Oak 31.68'
- S 35° W NW side of 30" Oak 32.50'
- North E side of 12" Elm 23.79'
- East 1/2" Rebar (SW corner Section 34, T6N, R1W, Victor Twp) 87.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1/2" Rebar over 1" bar
- S 45° E Nail & Tag #16053 in NE side of 34" Oak 31.69'
- S 35° W Nail & Tag #16053 in NW side of 30" Oak 32.53'
- East 1/2" Rebar (SW corner Section 34, T6N, R1W, Victor Twp) 87.78'

Accepted existing monumentation location and set Standard Clinton County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (Next NW corner Section 3)
- Standard Clinton County Monument
- S 45° E Nail & Tag #16053 in NE side of 34" Oak 31.69'
- S 35° W Nail & Tag #16053 in NW side of 30" Oak 32.53'
- East Standard Clinton County Monument (SW corner Section 34, T6N, R1W, Victor Twp.) 87.78'
- N 45° W 1/2" Rebar 17.68'

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 1/19/94

Signed by *Dwight R. Schofield*
Surveyor's Michigan License No. 34976

Date January 12, 1994

