

JAN 27 2000

SECTION

CLINTON COUNTY REMONUMENTATION
SOUTH 1/4 CORNER OF SECTION 34, T5N, R1W,
BATH TOWNSHIP, CLINTON COUNTY, MICHIGAN.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 331

For corners in
CLINTON
(County)

Located In: Corner Code #

1. Public Land Survey T 5N R 1W H-13
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
DEC 21 12 47 PM '99
REG. OF DEEDS
CLINTON COUNTY, MICH.
David Wooley
Register of Deeds Stamp & File Number

I, Arden S. Pierson, in a field survey on 7/29/99
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

TOWNSHIP BOUNDARY SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR IN 1826
40.00 (CHAINS) SET H.M.P. B.O. 11" - N30°E - .44 (29.04')
D.O. 8" - N66°W - .53 (34.98')

(SEE BACK OF SHEET)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" ROD IN CONCRETE MONUMENT CONSISTENT WITH LCRC FILED IN LIBER 2, PAGE 266, AND ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

SET STANDARD CLINTON COUNTY MONUMENT WITH CARSONITE MARKER NORTH

*STANDARD CLINTON COUNTY MONUMENT IS A 2 1/2" DIAMETER STEEL TUBE, 30" LONG WITH A STAMPED BRASS CAP AND A BREAKAWAY MAGNETIC BASE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13
SOUTH 1/4 CORNER OF
SECTION 34, T5N, R1W,
STANDARD CLINTON COUNTY MONUMENT
WITH CARSONITE MARKER
2' WEST OF WEST EDGE MARSH ROAD ASPHALT
INGHAM COUNTY CORNER - EAST - 23.05'
NAIL & TAG #25832 IN NE SIDE 28" LOCUST - N62°W - 24.84'
NAIL & TAG #18998 IN SW SIDE 36" LOCUST - N45°W - 33.56'
NAIL & TAG #18998 IN NW SIDE 25" W. PINE - N81°E - 47.31'
CENTER MICHIGAN BELL TELEPHONE MANHOLE COVER - S82°W - 12.29'

G-13 889°43'46"W 2651.10'
I-13 N89°30'40"E 2666.26
BEARINGS BASED ON SOLAR OBSERVATION TAKEN AT M-13



Signed by *Arden S. Pierson* Date 11/02/99
Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/11/99
[Signature]

SECTION

H-13 SOUTH ¼ CORNER OF SECTION 34, T5N, R1W, BATH TOWNSHIP, CLINTON COUNTY, MICHIGAN

LCRC LIBER 001, PAGE 607, DATED DECEMBER 26, 1972 BY RONNIE LESTER PS#18998
 "H-13" - FOUND CORNER AS CALLED FOR IN MDSH RECORDS FOUND P.K. NAIL NE SIDE TELEPHONE POLE -NW- 54.93'

FOUND P.K. NAIL SOUTHSIDE 15' PINE -ENE- 47.47'
 FOUND P.K. NAIL AND MOSH TAG EAST SIDE 24" TREE -NE- 24.44'
 LCRC LIBER 2, PAGE 266, DATED OCTOBER 17, 1979 BY RONNIE LESTER PS# 18998 (INGHAM COUNTY SURVEY AND REMONUMENTATION PROJECT)
 EXCAVATED HOLE 5' x 5' TO AN AVERAGE DEPTH OF 2.0' ON THE WEST EDGE OF MARSH ROAD - FOUND ¼" ROD 14.0' ± WEST OF CENTERLINE OF MARSH ROAD (1" PIPE BENEATH)
 SET 4" x 36" CONCRETE MONUMENT WITH ½" x 38" REROD AND CAP #18998 IN LOCATION OF 1" PIPE
 NAIL & TAG #18998 NORTH SIDE 8" FENCE POST - WEST - 19.10'
 NAIL & TAG #18998 NORTH SIDE 24" BUTTERNUT - WNW - 25.17'
 NAIL & TAG #18998 SOUTH SIDE 24" LOCUST -NW- 33.80'
 NAIL & TAG #18998 NORTH SIDE 12" WHITE PINE -ENE- 47.57'
 CONCRETE MONUMENT COX H-1 MERIDIAN TOWNSHIP, T4N, R1W, INGHAM COUNTY -EASE- 23.03'

CERTIFIED BOUNDARY SURVEY - RECORDED IN LIBER 1, PAGES 266-269, DATED 12/18/72 BY RONNIE LESTER PS# 18998
 (SHOWS POSITION OF CORNER)
 SAME WITNESS AS LCRC LIBER 001, PAGE 607

CERTIFICATE OF SURVEY RECORDED IN LIBER 1, PAGES 452-453, DATED FEBRUARY 15, 1974 BY MARVIN F. FOUTY, PS# 18989
 (SHOWS POSITION OF CORNER) FOUND PIPE
 FOUND P.K. NAIL NE SIDE TELEPHONE POLE -NW- 54.93'
 FOUND P.K. NAIL SOUTH SIDE 18" PINE - ENE- 47.471
 FOUND P.K. NAIL & MDSH TAG EAST SIDE 24" TREE -NE- 24.44'

CERTIFICATE OF SURVEY RECORDED IN LIBER 2, PAGE 483, DATED 4/23/82 BY JAMES E. STEPHENS PS# 16053
 (SAME WITNESS AS LIBER 2, PG. 470)

CERTIFICATE OF SURVEY RECORDED IN LIBER 2, PAGE 813, DATED AUGUST 9, 1985 BY LAVERNE J. HENDRYX PS# 3276

(SHOWS POSITION OF CORNER)
 CERTIFICATE OF SURVEY RECORDED IN LIBER 2, PAGE 814, DATED SEPTEMBER 27, 1983 BY LAVERNE J. HENDRYX PS# 3276
 (SHOWS POSITION OF CORNER)

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 23-24 DATED 6/30/87 BY LARRY A. BRYAN PS# 25832
 FOUND CONCRETE MONUMENT 1.5' WEST EDGE PAVEMENT OF MARSH ROAD

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 541-543, DATED 3/29/89 BY LARRY A. BRYAN PS# 25832
 (SHOWS POSITION OF CORNER)

FOUND CONCRETE MONUMENT 1.5' WEST OF WEST EDGE PAVEMENT MARSH ROAD
 FOUND CONCRETE MONUMENT IN MONUMENT BOX, NORTH ¼ CORNER SECTION 3, T4N, R1W, 23.10'
 FOUND NAIL & TAG #18998 IN NORTH SIDE 15" PINE -N80°E - 47.55'
 FOUND NAIL & TAG #18998 IN NORTHEAST SIDE 24" WALNUT -N60°W - 25.10'

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 641-643, DATED 7/12/69 BY LARRY A. BRYAN PS# 25832

(SHOWS POSITION OF CORNER)
 WITNESSES SAME AS LIBER 3, PAGES 541-543
 SET NAIL & TAG WEST SIDE UTILITY POLE - S05°W - 82.11'
 FOUND MONUMENT IN MONUMENT BOX NORTH ¼ CORNER SECTION 3, T4N, R1W - EAST 23.10;

MDOT CONSTRUCTION PLANS FOR 1-69 - JOB NUMBER 02233A, DATED 7/25/85 LIST WITNESSES AND
 CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 712-713, DATED 4/20/88 BY LARRY A. BRYAN PS# 25832

(SHOWS POSITION OF CORNER)
 WITNESSES SAME AS LIBER 3, PAGES 541-543

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 740-742, DATED 1/06/88 BY LARRY A. BRYAN PS# 25832

(SHOWS POSITION OF CORNER)
 WITNESSES SAME AS LIBER 3, PAGES 541-543

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 802-803, DATED 11/12/87 BY LARRY A. BRYAN PS# 25832

(SHOWS POSITION OF CORNER)
 WITNESSES SAME AS LIBER 3, PAGES 541-543

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 3, PAGES 983-984, DATED 8/28/85 BY LARRY A. BRYAN PS# 25832

(SHOWS POSITION OF CORNER)
 WITNESSES SAME AS LIBER 3, PAGES 541-543

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 4, PAGE 911
 (SHOWS POSITION OF CORNER)

CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 5, PAGES 52-54, NO DATE BY LARRY A. BRYAN PS# 25832
 (SHOWS POSITION OF CORNER)
 WITNESSES SAME AS LIBER 3, PAGES 541-543

TOPOGRAPHICAL SURVEY RECORDED IN LIBER 721, PAGE 299 DATED 10/31/96 BY LARRY A. BRYAN PS# 25832
 (SHOWS POSITION OF CORNER)

FOUND CONCRETE MONUMENT 1.5' WEST OF MARSH ROAD ON EAST-WEST FENCE LINE
 FOUND NAIL & TAG #18998 SOUTH SIDE 24" TWIN WALNUT - N60°W - 33.71'
 FOUND NAIL & TAG #18998 NORTH SIDE 24" PINE - N80°E - 44.42'
 PROJECT COORDINATES FOR CORNER SAME WITNESSES AS LCRC LIBER 2, PAGE 266

MDOT 1956 MDOT CONSTRUCTION PLANS FOR M-78

WITNESSES FOR CORNER
 N58°E 111.00' SW CORNER HOUSE
 N80°E 38.30' 24" WALNUT
 N57°W 25.70' 18" WALNUT
 1" IRON PIPE

MDOT 1930 M-78 CONSTRUCTION PLANS
 (SHOWS COUNTY LINE)