

FEB 18 1998

SECTION

CLINTON COUNTY REMONUMENTATION
NORTHEAST OF SECTION 2 AND NORTHWEST OF SECTION 1, T5N-R1W
BATH TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 285

RECORDED

DEC 28 3 35 PM '98

REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Carol W...

Register of Deeds Stamp
& File Number

For corners in

Clinton (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>1W</u>	<u>K-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling In Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

I, Mark L. VanRaemdonck, in a field survey on January 27, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	4	5	6	7	8	9	10	11	12	13	14	15	16
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	20	21	22	23	24	25	26	27	28	29	30	31	32
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

- Original Hervey Parke, D.S. November 1826
Monument: Wood post 1.18 West of corner
Access: W. Oak 18 S76°E 49
Do 9 S64°W 67
- 7 1/2" x 9 1/2" Black Leather Notebook on file in County Drain Office (no names, no dates).
Monument: Not given.
Access: W. Oak 18 N23 1/4°E .58 3/4
W. Oak 7 S19 3/4°W .34 1/2

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found no evidence of original corner monument or accessories. I re-established this corner location on the standard township line between corners J-13 and K-13, T6N-R1W at the G.L.O. distance of 1.18 chains (77.88 feet) West of corner K-13, T6N-R1W. I found no conflicting evidence at this location and accepted it as the careful and faithful re-establishment of the original corner position. There is a tree line running South at this location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:
Set a Standard Clinton County Remonumentation Monument, being a 2 1/2" diameter steel tube, 30" long with a stamped brass cap stamped, P.S. 24622 and a breakaway magnetic base, at the location described in Section B above. The monument is witnessed by the following accessories:

- N80°W 108.31' Set N&T #24622 S. face 18" Walnut
- South 33.75' Set N&T #24622 E. face 24" Oak
- S55°E 69.31' Set N&T #24622 W. face util. pole
- N40°E 38.43' Set N&T #24622 W. face util. pole
- N89°39'58"E 77.88' Remon. Monument at corner K-13, T6N-R1E
- S89°39'58"W 2565.75' Remon. Monument at corner J-13, T6N-R1E

Bearing to corners K-13 and J-13 are based on a solar observation taken near the SE corner of Section 36, T6N-R1W.



Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date SEPT 24, 1998
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 7/29/98
g f o