

**SURVEY &
REMONUMENTATION**

APR 27 1995 E 1/4 CORNER OF SECTION 24, BATH TWP.

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Clinton

(County)

Located In:

Corner Code -#

1. Public Land Survey	T	<u>5N</u>	R	<u>1W</u>	<u>M-8</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

DEC 12 12 00 PM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Arden S. Pierson

LIBER 4, PAGE 42

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Arden S. Pierson PS in a field survey on March 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
M-8 - Original survey by Harvey Parke DS, 1826.
Recorded in Liber 2, Page 679, by Donald L. Bissell PS #18655, dated July 13, 1988. "Set 4"x 36" concrete mon. at intersection of old fences North-South and West." As shown on the certified survey map recorded in Clinton County Records. With Witnesses:
N30°E - 24.40' - 6" Maple
S78°E - 20.21' - 5" Maple
S83°W - 27.18' - 6" W. Ash
N21°W - 7.78' - 10" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 18, Bath Township

M-8 - Found 4"x 36" concrete monument with brass disc at intersection of old fences. And is accepted as the best available evidence of the position of the original corner. Michigan Department of Natural Resources Monument left in place.

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 11/9/94
JFS



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 (E 1/4 corner of Section 24)
concrete monument

DNR Survey tag in N. side 10" Box Elder -S80°W- 27.06'
DNR Survey tag in E. side 18" Maple -N15°W- 7.72'
DNR Survey tag in S. side 10" Maple -N32°E- 24.34'
DNR Survey tag in N. side 10" Maple -S77°E- 20.22'

Signed by *Arden S. Pierson*
Surveyor's Michigan License No. 13039

November 1, 1994