

**SURVEY &
REMONUMENTATION**

APR 27 1995

**COMMISSION SE CORNER OF SECTION 25, BATH TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Clinton
(County)

Located In:

Corner Code #/

- | | | | | | |
|---------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>5N</u> | R | <u>1W</u> | <u>M-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

LIBER 4, PAGE 44

RECORDED

DEC 12 12 00 PM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Rowe

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

Arden S. Pierson PS. in a field survey on March 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 - Original survey by Harvey Parke DS, 1826.

*(SEE BACK OF SHEET)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 25, Bath Township

M-11 - Found 1/2" rod, North of North face of 30" Oak. And is accepted as the best available evidence of the position of the original corner. Removed 1/2" rod and replaced it with Standard Clinton County Monument - placed rod next to monument below brass cap.

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 11/9/94
[Signature]



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 (SE corner Section 25)
1/2" rod

- Nail & MDOT tag in NW side dead 16" W. Cherry -S48°W- 4.84'
- West edge survey marker post -North- 2.55'
- Nail & MDOT tag in N. side 26" Oak -N78°W- 15.69'
- Nail & tag W. in W. side 17" Maple -N05°- 31.14'
- Nail & tag in S. side 11" Elm -N84°E- 16.28'

*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base.

Signed by *Arden S. Pierson* Date NOVEMBER 1, 1994

Surveyor's Michigan License No. 13039