

MICHIGAN DEPARTMENT OF NATURAL RESOURCES - FOREST MANAGEMENT DIVISION  
LAND CORNER RECORDS  
Report printed November 12, 1993

TSM -R1W Section: 26 Corner Code: 9 County: Clinton Record date: 8/27/1992  
East 1/16 corner. Surveyors: Gary C. Bilow  
Description of original monument and accessories and/or restoration: Date surveyed: March 03, 1992  
9: Corner not established in original government survey. Found no Record numbers: 157  
subsequent record.

Description of evidence found and/or method of restoration: Description of monument and accessories:  
9: Established corner midway on line between East 1/4 corner and the  
calculated Center 1/4 corner. 9: Set 1/2" x 3/8" rebar encased in a 4"  
diameter concrete cylinder and capped  
with a cast aluminum Michigan  
Department of Natural Resources Tablet  
S52W 11.72', Nail & Tag in 8" Oak  
S8E 3.27', Nail & Tag in 6" Cherry  
S42E 15.60', Nail & Tag in 14" Willow  
N30E 20.05', Nail & Tag in 19" Oak

TSM -R1W Section: 26 Corner Code: 15 County: Clinton Record date: 8/27/1992  
West 1/16 corner on South line of Section. Surveyors: Gary C. Bilow  
Description of original monument and accessories and/or restoration: Date surveyed: August 23, 1991  
15: Found 3/8" rebar in a monument box 21.95' south of the section line Record numbers: 158  
formed by corners I-11 and J-11. DID NOT ACCEPT THIS CORNER.

Description of evidence found and/or method of restoration: Description of monument and accessories:  
15: Established corner midway on line between corners I-11 and J-11. 15: Set 1/2" x 3/8" rebar in cased in 4"  
diameter concrete cylinder and capped  
with a cast aluminum Michigan  
Department of Natural Resources Tablet  
in a monument box  
S53E 43.58', Fx & Tag in Utility Pole  
S1W 21.95', 3/8" rebar in monument box  
N22E 106.91', Fx & Tag in Utility Pole  
N35W 64.51', Steel Fence Post

TSM -R1W Section: 26 Corner Code: 16 County: Clinton Record date: 8/27/1992  
East 1/16 corner on South line of Section. Surveyors: Gary C. Bilow  
Description of original monument and accessories and/or restoration: Date surveyed: March 03, 1992  
16: Corner not established by original government survey. Found no Record numbers: 159  
subsequent record.

Description of evidence found and/or method of restoration: Description of monument and accessories:  
16: Established corner midway on line between corners J-11 and K-11. 16: Set 1/2" x 24" capped rebar in a  
monument box  
N25W 36.28', Nail & Tag in 15" Willow  
North 42.45', Nail & Tag in 30" Oak  
N45E 48.28', Nail & Tag in 12" Oak  
S20W 24.26', Nail & Tag in 14" Oak