

TSW -R1W Section: 26 Corner Code: 11 County: Clinton
Southwest 1/16 corner.
Description of original monument and accessories and/or restoration:
11: Corner not established by original government survey. Found no subsequent record.

Record date: 8/27/1992
Surveyor: Gary C. Bilow
Date surveyed: February 13, 1992
Record number: 160

Description of evidence found and/or method of restoration:

11: Established corner at the intersection of lines from corners 10 to 12 and 8 to 15. Corners 8 and 15 are recorded this date. Corner 10 was calculated to be midway on line between I-11 and calculated corner I-10. Corner 12 was calculated to be midway on line between J-11 and calculated corner J-10.

Description of monument and accessories:

11: Set 1/2" x 24" capped rebar in a monument box
N85E 22.12', Nail & Tap in 14" Elm
N81W 37.92', Nail & Tap in wood post
S33W 64.59', Nail & Tap in 5" Elm
S34E 63.56', Nail & Tap in twin 4" Elm

TSW -R1W Section: 26 Corner Code: 1 County: Clinton
West 1/16 corner on North line of Section.
Description of original monument and accessories and/or restoration:
1: Found 1/2" iron in monument box 11.4' to the North and 2.1' West of the mid point of the line as established by corners I-9 and J-9. DID NOT ACCEPT THIS CORNER.

Record date: 8/27/1992
Surveyor: Gary C. Bilow
Date surveyed: March 02, 1992
Record number: 161

Description of evidence found and/or method of restoration:

1: Established corner midway on line between corners I-9 and J-9.

Description of monument and accessories:

1: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet in a monument box
N10W 11.59', 1/2" iron in monument box
N41W 59.36', Nail & Tap in Utility Pole
S45E 50.67', Nail & Tap in 27" Oak
N62E 82.76', Nail & Tap in 27" Maple

TSW -R1W Section: 26 Corner Code: 8 County: Clinton
West 1/16 corner.
Description of original monument and accessories and/or restoration:
8: Corner not established by original government survey. Found no subsequent record.

Record date: 8/27/1992
Surveyor: Gary C. Bilow
Date surveyed: February 13, 1992
Record number: 162

Description of evidence found and/or method of restoration:

8: Established corner midway on line between calculated corners I-10 and J-10.

Description of monument and accessories:

8: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet in a monument box
S83W 66.79', Nail & Tap in 27" Oak
S47W 48.1' (slope distance), Sign Fast
S71E 54.78', Nail & Tap in 14" Cherry
N28W 75.48', Nail & Tap in 14" Pine