

T5W -R1W Section: 26 Corner Code: 4 County: Clinton
Northwest 1/16 corner.
Description of original monument and accessories and/or restoration:
4: Corner not established by original government survey. Found on subsequent record.

Record date: 8/27/1992
Surveyor: Gary C. Bilow
Date surveyed: February 13, 1992
Record number: 163

Description of evidence found and/or method of restoration:
4: Established corner at the intersection of lines formed by corners 3 to 5 and 8 to 1. Corners 8 and 1 are recorded this date. Corner 3 was calculated to be midway on line between corner 1-9 and calculated corner 1-10.

Description of monument and accessories:
4: Set 1/2" x 24" capped rebar in a monument box
S71W 37.89', Nail & Tag in 6" Elm
N75E 41.22', Nail & Tag in 10" Maple
S57E 35.14', Nail & Tag in 16" Oak
S30E 44.79', Nail & Tag in 12" Willow

T5W -R1W Section: 26 Corner Code: MC S. of 19 County: Clinton
Description of original monument and accessories and/or restoration:
MC S. of 1-9: Post established by U.S. Government Deputy Surveyor H. Parke in 1826 - accessories: S84E 28 links Tamarack 7 and N81W 38 links Tamarack 4.

Record date: 8/28/1992
Surveyor: Gary C. Bilow
Date surveyed: September 11, 1991
Record number: 164

Description of evidence found and/or method of restoration:
MC S. of 1-9: Corner reestablished by prorating the GLD distance to the measured distance between corners 1-11 and 1-9 and placing the corner on the line between those corners.

Description of monument and accessories:
MC S. of 1-9: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet in a 10" length of PVC pipe filled with concrete
N85E 8.98', Nail & Tag in 4" Elm
S43E 7.15', Nail & Tag in 3" Tamarack
S89W 13.22', Nail & Tag in 8" Maple
NDE 15.62', Nail & Tag in 8" Tamarack

T5W -R1W Section: 26 Corner Code: MC N. of 111 County: Clinton
Description of original monument and accessories and/or restoration:
MC N. of 1-11: Post established by U.S. Government Deputy Surveyor H. Parke in 1826 - accessories: S50E 14 links Tamarack 9 and N28E 16 links Tamarack 5.

Record date: 8/28/1992
Surveyor: Gary C. Bilow
Date surveyed: September 10, 1991
Record number: 165

Description of evidence found and/or method of restoration:
MC N. of 1-11: Corner reestablished by prorating the GLD distance to the measured distance between corners 1-11 and 1-9 and placing the corner on the line between those corners.

Description of monument and accessories:
MC N. of 1-11: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet
S10W 22.35', Nail & Tag in 14" Maple
S17E 6.13', Nail & Tag in 10" Maple
N45W 1.55', Nail & Tag in 12" Butternut
N20E 2.30', Nail & Tag in 12" Maple