

TSM -R1W      Sections      Corner Code: I11      County: Clinton      Record date: 8/26/92  
Section corner common to Sections 26-27-34-35.

Surveyors: Gary C. Silow  
Date surveyed: June 17, 1991  
Record numbers: 166

**Description of original monument and accessories and/or restorations:**

I-11: Post established by U.S. Government Deputy Surveyor H. Parke in 1826 - accessories: S33.5E 137.5 links Tamarack 14 and S82W 368 links Aspen 16. Department of Conservation Surveyor A. McCann (LS #13036) reestablished corner in 1964 as set 1-1/2" iron with 4" brass cap in fence line - accessories: N3W 17.60' spike in 28" Elm, South 15.55' spike in 8" Cherry, and West 1.0' a fence post. In 1973 J. Porter (LS #19003) recorded corner in Liber 1 Page 751. In 1982 Michigan Department of Transportation documented corner on I-69 Highway Plans (job N 02233a, cont. sec. #19042, sheet 510-12).

**Description of evidence found and/or method of restoration:**

I-11: Found 1" pipe with 4" brass cap and recovered two (2) accessories by L. Bryant (LS #25832). Accepted this iron as the best evidence of the original GLO post.

**Description of monument and accessories:**

I-11: Found 1" pipe with 4" brass cap  
N83W 11.51', Nail & Tag in 16" Maple  
N7W 6.22', Nail & Tag in 8" Elm  
S29E 74.74', Nail & Tag in 12" Elm  
S12E 62.18', Nail & Tag in 8" Elm

TSM -R1W      Sections      Corner Code: J11      County: Clinton      Record date: 8/25/1992  
Quarter corner common to Sections 26-35.

Surveyors: Gary C. Silow  
Date surveyed: June 14, 1991  
Record numbers: 167

**Description of original monument and accessories and/or restorations:**

J-11: Post established by U.S. Government Deputy Surveyor H. Parke in 1826 - accessories: N54E 21 links White Oak 18 and S52W 40 links White Oak 16. Corner recorded in 1975 by E. Brewer (LS #06515) in Liber 1 Page 933 as set 3/4" iron pipe at the intersection of lines formed between corners I-11 and N-11 and the projected North-South 1/4 of Section 35 - accessories: S83-3/4W 95' center 24" Hickory, S80-1/4E 83' center 24" Hickory, and N43E 139' center Power Pole.

**Description of evidence found and/or method of restoration:**

J-11: Found 3/4" iron and three (3) accessories by J. Stephens (LLS 16053). Accepted 3/4" iron as the best evidence of the original GLO post.

**Description of monument and accessories:**

J-11: Replaced 3/4" iron with 1/2" x 36' rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet in a monument box  
N72W 182.52', Nail & Tag in 4" Poplar  
N47W 168.58', Nail & Tag in Power Pole  
N57E 173.80', Nail & Tag in Power Pole  
S14E 30.49', Nail & Tag in 4" Pine