

TSM -R1W Section: Corner Code: K11 County: Clinton
Section corner common to Sections 25-26-35-36.

Record date: 8/28/1992
Surveyor: Gary C. Kildow
Date surveyed: February 10, 1991
Record number: 168

Description of original monument and accessories and/or restoration:

K-11: Post established by U.S. Government Deputy Surveyor H. Parke in 1826
- accessories: N41W 81.5 links Black Oak 12 and S14E 82 links White Oak 6.
Corner recorded in Liber 1 Page 205 in 1971 by W. Jones (LS #02934) as
"found 1" pin buried 1' below road surface from a 1929 Highway witness -
accessories: set monument box. N61W 29.72' Oak 34", S26E 33.40' Box Elder
21", S36W 33.00' Oak 34", and S15W 100.32' Northeast corner house
foundation."

Description of evidence found and/or method of restoration:

K-11: Found 1" iron and but none of Jones's accessories due to I-69
Highway construction. Iron is approximately 68' East and 38' North of
Mile 96 Sign Post on the North side of West bound I-69 Highway. Compared
distances to corners K-10 and J-11 and found them to be reasonable and
consistent with recorded data. Accepted this corner as the best evidence
of the original GLO post.

Description of monument and accessories:

K-11: Found 1" iron with cap (#28409)
N70E 189.18', Center of "x" on North
edge I-69 Highway at Station 568+00
S38W 122.70', Center of "x" on North
edge I-69 Highway at Station 565+00
S40W 77.31', Highway Mile 96 Sign Post
S60W 168.79', Chisled "x" on Northeast
end of Concrete Culvert
West 194.7'. Steel fence post

TSM -R1W Section: Corner Code: K10 County: Clinton
Quarter corner common to Sections 25-26.

Record date: 8/28/1992
Surveyor: John Spencer
Date surveyed: January 01, 1991
Record number: 169

Description of original monument and accessories and/or restoration:

K-10: Post established by U.S. Government Deputy Surveyor H. Parke in 1826
- accessories: S25E 8 links White Oak 12 and N53E 31 links Yellow Oak.
Clinton County Surveyor Charles Eddy in 1900 records 1 (one) witness -
N1-1/2E 48 links Hickory 8". Corner recorded in 1982 in Liber 2 Page 457
by J. Spencer (LS #13044) as set 3/4" iron pipe on line between Southeast
and Northeast section corners - accessories: North 30.34' Sassafras 7",
West 17.31' Cherry 10", S30E 10.68' triple Cherry 30", and S5W 16.20'
Cherry 13".

Description of evidence found and/or method of restoration:

K-10: Found 3/4" iron pipe and recovered all of Spencer's witnesses.
Accepted this corner as the best evidence of the original GLO post.

Description of monument and accessories:

K-10: Found 3/4" iron pipe
North 30.82', Nail in 7" Sassafras
West 17.31', Nail in 10" Cherry
S30E 10.31', Nail in 30" triple Cherry
S5W 16.20', Nail in 13" Cherry