

TSM -R1W Section: Corner Code: I9 County: Clinton
Section corner common to Sections 22-23-26-27.

Record date: 8/28/1992
Surveyor: Gary C. Gilow
Date surveyed: June 04, 1991
Record numbers: 170

Description of original monument and accessories and/or restoration:

I-9: Corner established by U.S. Government Deputy Surveyor H. Farke in 1826
- accessories: S88W 65 links Yellow Oak 16 and S68E 27 links Yellow Oak
20. Corner recorded in Liber 2 Page 203 by J. Porter (LS #19003). From
MDOG field notes for I-69 construction dated 6/24/82 - found 3/4" iron
pipe - accessories: N20E 22.48' wood post, S20E 20.71' Oak clump 28', S60W
35.43 Oak 21', and N15W 74.05 Southeast corner of house.

Description of evidence found and/or method of restoration:

I-9: Found 3/4" iron pipe and recovered all MDOG witnesses. Accepted this
corner as the best evidence of the original GLO post.

Description of monument and accessories:

I-9: Found 3/4" iron pipe
N20E 22.48' . Nail in Wood Post
S20E 20.71' . Nail in 28" Oak clump
S60W 35.43' . Nail in 21" Oak
N15W 74.05' . Southeast corner of house

TSM -R1W Section: Corner Code: J9 County: Clinton
Quarter corner common to Sections 23-26.

Record date: 8/28/1992
Surveyor: Gary C. Gilow
Date surveyed: June 04, 1992
Record numbers: 171

Description of original monument and accessories and/or restoration:

J-9: Post established by U.S. Government Deputy Surveyor H. Farke in 1826
- accessories: N17E 19 links Yellow Oak 10 and S52W 39 links White Oak 24.
From MDOG field notes in 1971 by A. Pierson (LS #13039) "Found broken
brick, small stones, and remains of charred wood - Set 1/2" copperweld rod
and monument box with stones around - accessories: N50W 39.06' triple
Maple 28", S5W 67.30' Oak 30", and N80E 68.86' Cedar clump 28" - W. Jones
(LS #02934) recorded this in Liber 1 Page 201." From MDOG project plans of
I-69 dated 1982 - Found 1/2" rod in monument box and all previous MDOG
witness and added N42W 73.10' Pine 6".

Description of evidence found and/or method of restoration:

J-9: Found 1/2" rod in monument box and recovered all MDOG witness.
Accepted this corner as the best evidence of the original GLO post.

Description of monument and accessories:

J-9: Found 1/2" rod in monument box
N50W 39.06' . Nail in 28" triple Maple
S5W 67.30' . Nail in 30" Oak
N80E 68.86' . Nail in 28" Cedar clump
N42W 73.10' . Nail in 6' Pine