

TSM -R1W Section: Corner Code: K9 County: Clinton Record date: 8/28/1992

Section corner common to Sections 23-24-25-26.

Surveyor: Gary C. Gilow

Date surveyed: June 09, 1992

Record number: 172

Description of original monument and accessories and/or restorations:

K-9: Post established by U.S. Government Deputy Surveyor H. Farke in 1826
- accessories: N56W 22.5 links white Oak 26 and N59E 37 links White Oak
20. Corner recorded in Liber 1 Page 53 by D. Scott (LS #12029) in 1971 as
found 1" pin set in 1-1/2" well point in centerline of existing road 6"
below gravel - accessories: S15E 22.22 Hickory 26", N30E 22.95' Hickory
26", North 28.82' wood fence post. Corner recorded in Liber 1 Page 203 by
W. Jones (LS #02934) in 1971 as "Found same as Scott but adds in Part B
"also basket of stones and steel ring around pipe" and adds one witness -
N65W 64.24 Hickory 23".

Description of evidence found and/or method of restoration:

K-9: Found 1" iron in monument box and all recorded witnesses. Accepted
this corner as the best evidence of the original GLO post.

Description of monument and accessories:

K-9: Found 1" iron in monument box
S15E 22.22". Nail in 26" Hickory
N30E 22.95". Nail in 26" Hickory
N65W 64.24". Nail in 23" Hickory
North 28.82". Nail in 6" Pine