

(55)

3-31-71

NORTH 1/4 COR.  
SEC. 33

- S. 1/4 COR. SEC. 28

INTERSECTION OF  
STATE AND PARK LAKE

FD. RR. SPIKE - FLUSH W/BIT  
PROPERTY OWNER STATES  
THERE WAS A CONC. MON.  
40 YEARS AGO. SURVEYOR  
BATEMAN USED CORNER

N. 20° W - 73.80' - SE. COR. BLOCK - BLDG # 15978  
N. 70° E - 75.79' - SW. COR. BRICK GAS STATION  
S. 40° E - 48.78' - T. POLE & P. POLE.

(AGREES) STEPHAN KNOX  
4-29-71

CO. WITNESSES

N 31° 45' W	50.0'	IRON PIPE
N 59° E	50.0'	IRON PIPE
S 29° 30' E	50.0'	IRON PIPE
S 21° 45' W	61.2	12" EIM

4-30-71

20 CHAINS NORTH - SET STONE  
S. 38 W - 42 LINKS - 5" APPLE  
2772'

5-18-71 - REMOVED R.R. SPIKE - DUG  
DOWN 5' DEEP. DIDNT FIND ANY-  
THING MORE. SET 1/2" CONCRETE  
ROD AND MON BOX.