

(59)

3-31-71

60

SOUTH 1/4 COR.
SEC. 25

-N 1/4 COR. SEC 36

INTERSECTION OF
PEACOCK AND STATE

FD.- STEEL FE. POST "T"
FLUSH W/SURFACE
IN CENTER OF STATE RD.
4' EAST OF EXISTING CENTER
OF PEACOCK RD.

N. 15° E. 73.24' - 15" W. CHERRY
N. 50° W. 54.72' - P. POLE
S. 65° W. 75.70' - "T. MAPLE
S. 20° E. 66.42' - N.W. COR - CONC. STEP

SEPT 25-1929 WITNESSES

LARGE STONE WITH X CUT
ON HIGH POINT.

18" ELM - S. 18° E - 60.5
4" ELM - S. 50 1/2° W - 44.5
5" HICKORY - N. 63 1/2° W - 49.0
24" B. OAK - N. 41 1/2° E - 24.5

} GONE

5-14-71 - BREWER PINS. FOUND
CHISELED CROSS IN TOP OF
STONE, RAISED WITH "T" IRON
MAY 1, 1955. CHECKED BREWER
WITNESSES - O.K.
DUG AROUND "T" IRON AND
SET MON. BOX W/ STONES
AROUND BOX.