

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Clinton
(County)

Located In:

Corner Code ~~##~~

- | | | | | | | | |
|------------------------------------|---|-----------|---|-----------|-------|-----------|-------------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| 2. Property Controlling in Section | S | <u>26</u> | T | <u>5N</u> | R | <u>1W</u> | <u>3</u> |
| | S | _____ | T | _____ | R | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | <u>26</u> | T | <u>5N</u> | R | <u>1W</u> | <u>Prop</u> |
| | S | _____ | T | _____ | R | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Pro January 25, 1993

I, Gary C. Bilow, in a field survey on 3 January 24, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

3: Corner not established by original government survey. Found no record of corner ever being established.
Prop: Found no record of corner ever being established.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3: Established corner midway on line between corner I-9 and the calculated West 1/4 corner I-10.
Prop: Established property controlling corner on the East-West 1/4 line at its intersection with the GLO Meander Line of Mud Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



3: Set 4" State of Michigan Brass Cap on 9' of 1" iron pipe
S85E 52.89', Nail & Tag in clump of 5 4" to 8" Maples
N10E 19.96', Nail & Tag in 5" Elm
S10E 7.64', Nail & Tag in 4" Elm
S55W 27.80', Nail & Tag in 5" Elm

Prop: Set 1" x 132" iron pipe with 4" State of Michigan Brass cap in 4" x 10' PVC pipe filled with concrete
N30W 9.28', Nail & Tag in 4" Tamarack
S61W 17.38', Nail & Tag in 5" Tamarack
S14E 8.49', Nail & Tag in 4" Elm
N47E 11.93', Nail & Tag in 3" Tamarack
S45W 113'+/- to edge of water/marsh grass for Mud Lake

Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 2/2/93