

(11)

5-13-71 - DUG UP 1/2" REINFORCING
 ROD. FOUND 1" PIPE BURIED
 2' BELOW SURFACE OF ROAD,
 WITH BROKEN BRICK AND LARGE
 STONE ON WEST SIDE OF 1" PIPE
 RAISED w/ 1/2" COPPERWELD ROD.
 SET MON. BOX, 1' SOUTH OF 1/2 RWD

DIFFERENCE
 0.97'
 N. 83° E

1" PIPE WITH
 1/2" COPPERWELD ROD
 1/2" REINFORCING ROD
 (REMOVED)

N. 55° W - 44.56' - 16" WALNUT
 S. 55° W - 44.61' - 36" OAK
 S. 30° E - 57.52' - 14" B. ELDER
 NORTH - 22.51' - CENTER 2" STEEL
 COR. FE. POST

TEN RIV
 MDSH NOTES

H-7

(12)

3-29-71

NORTH 1/4 COR.
 SEC. 22
 1/4 COR. W.M. 15
 FD. 1/2" REINFORCING ROD
 1' SOUTH OF EXISTING
 CENTER OF ROAD

INTERSECTION OF
 CLARK AND ROBINSON SOUTH

NORTH 22.50' CENTER 2" STEEL
 COR. POST,

~~N. 60° W - 45.26' - 16" WALNUT
 S. 60° W - 45.26' - 36" OAK
 S. 20° E - 57.16' - 14" B. ELDER~~

4-29-71 - 1891 WITNESSES

SET STONE w/ BRICK
 N. 67° W 99 1/4 LINKS 7 6" B. WALNUT
 65.50