



19

3-29-71

N.E. COR. SEC. 23  
COMMON TO SECS 21, 13 & 14

BUGGED - NO LUCK  
EE, LINE SOUTH

5-19-71 - DUG HOLE - FOUND  
SMALL BASKET OF STONES  
5' BELOW SURFACE OF ROAD -  
BENEATH OLD DECAYED TREE  
ROOTS. 2' SOUTH OF EXISTING  
C OF CLARK ROAD. NUMEROUS  
LARGE STONES WERE SET  
OVER ORIGINAL BASKET OF  
SMALL STONES. W/ ONE LARGE  
POINTED STONE AND A 1/2"  
PIPE SET FOR THE SEC.  
CORNER. MON. BOX SET.

N. 55° E - 44.94' - 23" OAK  
S. 20° W - 28.74' - 11" OAK  
N. 25° W - 48.85' - 15" OAK  
N. 65° W - 73.19' - 18" OAK

X-7  
T5N, R1W  
MDSH - NOTES