



39

E-30-71

EAST 1/4 COR.  
SEC. 21

- W. 1/4 COR SEC. 22

INTERSECTION OF  
DRUMHELLER AND CENTER

FD. - 3/4" PIPE

2' NORTH OF EXISTING CENTER OF ROAD

S. 60° W - 48.47' - 10" CEDAR

N. 60° E - 96.30' - 21" OAK

S. 35° E - 89.40' - T. POLE

S. 40° W - 111.58' - N.E. COR - CONC. FLX. PORCH  
HOUSE #6952

SOUTH - 32.91' - 3/4" PINCH PIPE

4-29-71 - 301 WITNESSES

FOUND STONE - SET CROCKERY AROUND IT  
HOLE

5-10-71 - DUG LARGE - FOUND SMALL  
AMOUNT OF CROCKERY AND  
BROKEN GLASS - NO OTHER  
EVIDENCE - ACCEPTED 3/4" PIPE

G-8  
T5N, R1W  
MDSH NOTES