

59

3-31-71

SOUTH 1/4 COR.  
SEC. 25

-N 1/4 COR. SEC. 36

INTERSECTION OF  
PEACOCK AND STATE

FD.- STEEL FE. POST "T"  
FLUSH W/SURFACE  
IN CENTER OF STATE RD.  
4' EAST OF EXISTING CENTER  
OF PEACOCK RD.

N. 15° E. 73.24' - 15" W. CHERRY  
N. 50° W. 54.72' - P. POLE  
S. 65° W. 75.70' - "T. MAPLE  
S. 20° E. 66.42' - NW. COR. CONC. STEP

SEPT 25-1929 WITNESSES  
LARGE STONE WITH X CUT  
ON HIGH POINT.

18" ELM - S. 18° E - 60.5'  
4" ELM - S. 50 1/2° W - 44.5'  
5" HICKORY - N. 63 1/2° W - 49.0'  
24" B. OAK - N. 41 1/2° E - 24.5'  
GONE

60

5-11-71- BREWERY BINS. FOUND  
CHISELED CROSS IN TOP OF  
STONE, RAISED WITH "T" IRON  
MAY 1, 1955. CHECKED BREWER  
WITNESSES - O.K.  
DUG AROUND "T" IRON AND  
SET MON. BOX W/ STONES  
AROUND BOX.

L-11  
T S N, R I C  
M D S H N O T E S