

JAN 27 2000

LAND CORNER RECORDATION CERTIFICATE  
CLINTON COUNTY REMONUMENTATION  
WEST 1/4 CORNER, SECTION 18, T5N-R2W  
DEWITT TOWNSHIP  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 342

SECTION

For corners in

<u>Clinton</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 5N R 2W	A-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

Dec 21 12 49 PM '99

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Carol W. ...*  
Register of Deeds Stamp  
& File Number

I, Mark L. VanRaemdonck, in a field survey on, June 10, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- Original. Not a G.L.O. corner. No record was found of the original corner position.
- Marvin F. Fouty, L.C.R.C., recorded Liber 2, page 153, September 29, 1977.  
Monument: Set 1/2" bar and cap on line between Northwest and Southwest corner, Section 18 on possession line to the East.  
Accessories: Tag & Nail West side anchor post NNE 60.2'  
Tag & Nail East side 8" Cherry NNW 125.77'
- Marvin F. Fouty, Certified Survey, recorded Liber 1, page 973, September 29, 1977.  
Monument and accessories same as No. 2 above.
- Richard W. Steadman, Plat of "Looking Glass Pines No. 3" recorded Liber 8 of Plats, page 38-41, May 31, 1996.  
No monument or accessories are given. Refers to recording in Liber 2, page 853.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	20		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 9/8/99  
*J. ...*

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Fouty's 1/2" bar in monument box as referenced in No. 2 and 3 above. Found this 1/2" bar to be on the Standard Township Line. This location is 1.57 feet North of the split of the distance between corners A-5 and A-7, T5N-R2W. I accepted this monument as the careful and faithful establishment of the original corner position based on the best available evidence. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set a standard Clinton County Remonumentation monument, being a 2 1/4" diameter steel tube, 30" long with a standard brass cap, stamped "P.S. 24622", and a breakaway magnetic base at the corner location described in Section B above. The monument is witnessed by the following accessories:

- N85°E 30.84' Set N&T N. face util. Pole
- S65°E 34.32' Top cen. Tele. Ped.
- S20°E 50.97' N. face sign post
- S30°W 64.06' Fnd. N&T E. face 18" Elm
- N00°02'42"E 2626.64' Remon Monument at M-5
- S00°02'42"W 6.72' Remon Monument at M-6

Bearings to M-5 and M-6 are based on solar observations.

Signed by Mark L. VanRaemdonck  
Surveyor's Michigan License No. 24622

Date 12-16-99

