

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in  
Clinton  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 5N R 2W	A-9, A-13
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

MAR 15 3 37 PM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Carol Woolley*

LIBER 4, PAGE 16  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Arden S. Pierson P., in a field survey on October 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules hereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-9 - Original survey by Harvey Parke, D.S., in 1827, Chas E. Hollister, County Surveyor Records stone, with iron below June, 1880 - Recorded Corner in Liber 1, page 131.- Recorded by F. White P.S. in Liber 1, page 393.
- A-13 - Original survey by Harvey Parke D.S., in 1827, recorded in Liber 2, page 598 - MDOT survey notes record survey information for SE 1/4 Section 36, T5N, R3W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dewitt Township

- A-9 (SW corner-Section 19) - Found 1/2" rod in monument box @ South edge of pavement -East- Accepted monumentation and placed Standard Clinton County Monument in existing monument box.
- A-13 (SW corner-Section 31) - Found boatspike in monument box Verified with MDOT reference point - Excavated below and found boatspike buried 24"- Placed Standard Clinton County Monument and replaced monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 (SW corner-Section 19)	A-13 (SW corner-Section 31)
(Standard Clinton County Monument in monument box)	(Standard Clinton County Monument in monument box)
Watertown Twp. corner -North- 13.20'	Boatspike -North- 77.06'
N & T SW side power pole -N22°W- 107.73'	PK nail S. side telephone pole -N80°W- 31.70'
N & T NW side light pole -N69°E- 110.85'	N & T #16053 NW side telephone pole -N64°E- 52.83'
N & T #25832 SE side cut off utility pole -N24°E- 102.11'	N & T #16053 W. side power pole -S12°E- 85.20'
N & T #25832 SW side light pole -S35°E- 46.33'	N & T E. side power & telephone pole -S16°W- 154.95'

\*\*Standard Clinton County Monument is a 2" steel tube, 30" long with a 3/4" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson Date November 24, 1993  
 Surveyor's Michigan License No. 13039  
 APPROVED BY CLINTON COUNTY PEER GROUP  
 DATED 12/9/93

