

SURVEY & REMONUMENTATION

FEB 02 1998

REMONUMENTATION

SECTION

SECTION 6, DEWITT TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Clinton (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 2W	B-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Nov 4 1 25 PM '97

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Arden Pierson

LIBER 4 PAGE 244

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Arden S. Pierson, PS, in a field survey on July 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ This position not established by original government surveyors.
- ◆ LCRC by Larry A. Bryan, PS, #25832, dated February 15, 1985, Liber 2, Page 543. T5N, R2W, B-1, Set corner at proportional distance in accordance with GLO measurements on line between C-1 and A-1, Section 6, T5N, R2W. Witnessed by:
Set 1/2" bar & cap in centerline of Cutler Road on field separation South
Northwest corner pole barn - S30°E - 92.70'
Southwest corner barn - North - 125.50'
Set nail & tag South root of 24" Maple - N60°E - 87.00'

(over)

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/20/97
J.P.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron and cap #25832 in centerline Cutler Road 4" below gravel road surface, this position not established by original government surveyors, this monument is accepted as the best available evidence of the position of the corner.

Placed Standard Clinton County Monument (amended corner)
Standard corner for T6N, R2W is 22.10' East

C. Description of monument for corner and accessories established to perpetuate locating the position of _____

North 1/4 Corner of Section 6
*Standard Clinton County Monument

- Nail & tag #13039 in SW side Power Pole - S52°E - 29.08'
- Nail & tag #13039 in West side Light Pole - N04°W - 91.30'
- Nail & tag #13039 in SE side 30" Maple - N68°E - 87.10'
- Nail & tag #13039 in SE side Power Pole - N78°E - 115.18'
- To B-13, T6N, R2W: S89°25'24"E 22.10
- To B-1, T6N, R2W: N89°25'24"W 2790.55 From solar observations.

*Standard Clinton County Monument is a 2 1/2" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson* Date July 27, 1997
Surveyor's Michigan License No. 13039

◆Certified Boundary Survey by Larry A. Bryan, PS, #25832, dated January 3, 1990, Liber 3, Pages 550-552.

◆Boundary Survey by Arden S. Pierson, PS, #13039, dated June 15, 1996 (not recorded). ½" iron and Bryan cap. Witnessed by:

Nail & tag #13039 in SW side Power Pole - S50°E - 29.09'
NW Corner Pole Bldg. - S25°E - 92.66'

Nail & tag #13039 in S. side 24" Maple - N75°E - 87.10'

Nail & tag #13039 in W. side Light Pole - N05°E - 91.33'