

SURVEY & REMONUMENTATION

FEB 02 1998

REMONUMENTATION

SECTION

SECTION 6, DEWITT TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Clinton
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 5N | R | 2W | C-1 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Nov 4 1 26 PM '97

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carol W. Winkler

4 PAGE 246

LIBER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Arden S. Pierson, PS, in a field survey on June 24 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ Original survey by Hervey Parke, DS, 1826. Intersected Town Line 33 W., witnessed by W. Oak 18" - S74½°E - 32½ links; Beech 9" - S56°W - 18 links.
- ◆ Survey by H.H. Jenison, County Surveyor, March 27-29, 1878. Stone set, witnessed by: Apple 2" - N38½°W - 57 links.
- ◆ Clinton County Surveyor Witness Notes, stone set, witnessed by: Apple 2" - N38½°W - 57 links.

(OVER)

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/20/97
J. J. J.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ¾" pinched pipe (could not find stone as found in 1960's). Accepted pipe as amended corner and as a careful and faithful reestablishment of the position of the original corner. Set true corner monument on township line, the amended position is 0.33' South. [Standard corner for T6N, R2W, is 22.09' East.]

4' North of Physical Centerline of Cutler Road and 10' West of Norris Road South.

Set Standard Clinton County Monument with found pipe, placed on South side.

C. Description of monument for corner and accessories established to perpetuate locating the position of corner:

Northeast Corner of Section 6

*Standard Clinton County Monument and monument box

- Nail & tag #13039 in SE side Power Pole - N44°E - 177.26'
- Nail & tag #13039 in NW side Power Pole - S24°W - 124.14'
- Nail & tag #13039 in NW side 20" Walnut - S83°W - 122.70'
- Nail & tag #13039 in NE side Power Pole - N54°W - 52.36'
- To B-13, T6N, R2W - N89°52'36"W - 2612.76'
- To C-13, T6N, R2W - S89°52'36"E - 22.09'. From solar observations.

*Standard Clinton County Monument is a 2½" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson*

Date July 19, 1997

Surveyor's Michigan License No. 13039

◆LCRC by Larry A. Bryan, PS, #25832, dated January 9, 1990, Liber 2, Page 756. Found $\frac{1}{2}$ " pipe in centerline of Norris Road, extended South and 2' North of centerline of Cutler Road. Witnessed by:

Found nail & tag in South side Power Pole - N60°W - 52.40'

Found nail & tag North side 14" Walnut - S70°W - 122.50'

Set nail & tag #25832 East side 8" Elm - S20°E - 105.60'

Found $\frac{3}{4}$ " pipe (Southeast Corner Section 31, T6N, R2W) - East - 21.90'

◆Certified survey by Arden S. Pierson, PS, #13039, dated June 15, 1996 (not recorded). Found a $\frac{3}{4}$ " Pipe (2.64' North of pointed stone) witnessed by:

Nail & tag #13039 in NE side Power Pole - N58°W - 52.55'

Nail & tag #13039 in NW side 18" Walnut - S82°W - 122.68'

Nail & tag #13039 in NW side Power Pole - S27°W - 123.83'

Nail & tag #13039 in W side Guy Pole - S12°W - 153.76'