

**SURVEY &
REMONUMENTATION**

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Clinton
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>5N</u> R <u>2W</u> | <u>E-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Mar 15 3 37 PM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 17

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Arden S. Pierson P.S. in a field survey on November 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey Harvey Parke D.S. in 1827.

E-9 - Chas E. Hollister, County Surveyor, set stone in October, 1880.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dewitt Township

E-9 - Corner recovered in 1971, monument removed during sewer construction, monument replaced by Ed Morse (MDOT) in 1976 from witnesses - Found monument box ring - excavated and recovered 3/4" pipe in monument box. Placed Standard Clinton County Monument in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 (SW corner Sec. 21)
(Standard Clinton County Monument
in monument box)

- PK nail NE side 18" Oak -S23°E- 31.07'
- NW corner foundation -S12°E- 111.24'
- PK nail E. side power pole -S03°W- 33.50'
- PK nail & MDSH tag W. side telephone pole -N05°E- 23.74'

**Standard Clinton County Monument is a 2" steel tube, 30" long with a 3/2" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson

APPROVED BY Date November 24, 1993

Surveyor's Michigan License No. 13039

CLINTON COUNTY PEER GROUP
DATED 12/3/93

