

SURVEY & REMONUMENTATION

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in **COMMISSION**
Clinton
 (County)

JAN 24 9 45 AM '94

REGISTER OF DEEDS
 CLINTON COUNTY, MICH.
Carol Woolley

LIBER 4, PAGE 1

Register of Deeds Stamp & File Number

	Located In:	Corner Code #/
1. Public Land Survey	T <u>5N</u> R <u>2W</u>	<u>F-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Arden S. Pierson, D. on a field survey on October 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey Harvey Parke D.S. in 1827

F-8 - Not set in original survey - Set as SE corner of plat of Lookout Acres Subdivision.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dewitt Township

F-8 - Located position from retracement of previous survey, excavated found ½" pipe buried 30" - Accepted as corner position - Set Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-8 (Center Sec. 21)
 (Standard Clinton County Monument
 in monument box)

- Nail & Tag NE side telephone pole -N34°W- 51.23'
- Nail & Tag SE side guy pole -S59°W- 43.03'
- Nail & Tag SE side power pole -N58°E- 49.84'
- NE corner of garage -S11°E- 93.14'

**Standard Clinton County Monument is a 2" steel tube, 30" long with a 3½" breakaway magnetic base and stamped brass cap.

Signed by *Arden S. Pierson* Date November 24, 1993

Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY DEER GROUP
 DATED 12/8/93
J. J. J.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

