

**SURVEY &  
REMONUMENTATION**

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in COMMISSION  
Clinton  
(County)

Located In: Corner Code #

- |                                       |                         |            |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey                 | T <u>5N</u> R <u>2W</u> | <u>F-9</u> |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                         |            |
| 5. Private Claims _____               |                         |            |

Jan 24 9 45 AM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Carol Woolley*

LIBER 4, PAGE 2

Register of Deeds Stamp & File Number

I, Arden S. Pierson P.S. on a field survey on October 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey Harvey Parke D.S. in 1827

F-9 - Chas E. Hollister, County Surveyor, set stone in Oct. 1880.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Dewitt Township**

F-9 - Recorded corner in Liber 1, page 149 - Monument destroyed by sewer construction, - Remonumented corner from survey retrace-ment - Placed Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

F-9 (S 1/4 corner Sec. 21)  
(Standard Clinton County Monument  
in monument box)

5.2' South of Centerline pavement.  
Iron set by L. Bryan -North- 4.30'  
Center of manhole cover -N77°W- 48.07'  
Center N. end 15" culvert -N43°E- 35.75'  
Center S. end 15" culvert -S43°E- 28.29'

\*\*Standard Clinton County Monument is a 2" steel tube, 30" long with a 3/4" breakaway magnetic base and stamped brass cap

Signed by Arden S. Pierson Date November 24, 1993

Surveyor's Michigan License No. 13039

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 12/8/93  
*A 35*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

