

SURVEY & REMONUMENTATION

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in **COMMISSION**
Clinton
 (County)

Located In: Corner Code ##

1. Public Land Survey	T <u>5N</u> R <u>2W</u>	<u>G-1, G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MAR 15 3 38 PM '94

REGISTER OF DEEDS
 CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 18

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Arden S. Pierson P. in a field survey on November 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-1 - Original survey by Harvey Parke D.S., in 1827. Lead plug placed by MDOT and subsequently replaced by 3/4" pipe in monument box - Recorded in Liber 2 page 197
- G-5 - Original survey by Harvey Parke D.S., in 1827. Corner re-established by MDOT from existing surveys in 1967. Recorded as 1/2" rod & monument box in Liber 1, page 505 and Liber 2, page 292.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dewitt Township

- G-1 - Cutler & US-27 - Found 3/4" pipe in monument box - Accepted as corner
- G-5 - Found 1/2" rod in monument box - Accepted same as corner monumentation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 (Cutler Rd. & US-27)
 3/4" pipe in monument box

G-5 (Herbison & US-27)
 1/2" rod in monument box

SW corner concrete r/w marker -N75°E- 91.14'
 N & T SW side power pole N54°W- 81.59'
 NW corner of CB cover -S05°E- 36.55'
 Centerline S. bound lanes -West- 12.3'±
 Centerline N. bound lanes -East- 24.0'±
 N & T NE side telephone pole -N20°W- 128.13

Face round metal light pole @ base -N42°E- 74.67'
 Face round metal light pole @ base -S42°E- 76.60'
 N & T NW side power pole -S65°W- 102.76'
 N & T SW side power pole -S56°W- 106.63'

Signed by *Arden S. Pierson* APPROVED BY CLINTON COUNTY PEER GROUP Date 11-24-93
 Surveyor's Michigan License No. 13039 DATED 12/8/93

