

**SURVEY & REMONUMENTATION**

**FEB 02 1998**

**SECTION**

**REMONUMENTATION  
DEWITT TOWNSHIP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**LIBER 004 PAGE 199**

**RECORDED**

**Oct 17 9 11 AM '97**

REGISTERED DEEDS  
CLINTON COUNTY MICH.

For corners in

Clinton (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>2W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

I, Mark L. VanRaemdonck, in a filed survey on August 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1. Original Lucius Lyons 1/6/1827  
Mon: Wood Post  
Access: W. Oak 30 S75°E 65 ½  
DO 14 S63°W 88
2. Kay Don Fluke L.C.R.C. L. 2, P. 416 10/6/81  
Mon: Found ½" Bar & Cap #18989  
Access: Due East 15.18 ½" Bar & Cap in Mon. Box  
Due East 49.06 Conc. Monument  
S40°W 41.25 Tag in E. side of 18" Oak  
S25°E 60.55 R. R. spike in W. side 42" Oak
3. Richard Steadman, Cert. survey L. 4, P. 747 12/16/91  
Mon: ½" Iron Rod  
Access: Conc. monument West 49.06'  
18" Oak S40°W 49.06'  
42" Oak S25°E 41.25'  
½" Iron rod (Olive Twp Cor.) East 15.18

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Found ½" rerod & cap as referenced in No. 2 and 3 above accepted this position as the location of the original corner based on the best available evidence.

**C. Description of monument for corner and accessories to perpetuate locating the position of the corner**

Removed ½" Rerod & Cap and replaced it with a standard Clinton County Remonumentation Monument. The monument is witnessed by the following accessories:  
 N70W 27.92 Set Nail & Tag #24622 in N. face 12" Oak  
 S30W 40.41 Set Nail & Tag #24622 in N. face 24" Oak  
 S89°41'17"E 15.29 STD Clinton County Mon at K-13, T6N-R2W  
 North 148.4 Centerline asphalt pavement Round Lake Road  
 N89°41'17"W 2624.71 STD Clinton County Monument at J-13, T6N-R2W

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	25	23	22	27	28	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Mark L. VanRaemdonck  
 Surveyor's Michigan License No. 24622



Date SEPT 8, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS 1971  
 REVISION MAY 12 1988  
 REVISION JAN 1993

APPROVED BY  
 CLINTON COUNTY DEED GROUP  
 DATED 9/8/97