

FEB 18 1999

71

SECTION CLINTON COUNTY REMONUMENTATION EAST 1/4 CORNER SECTION 13, T5N, R2W, DEWITT TOWNSHIP, CLINTON COUNTY, MICHIGAN

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 292

Form with columns: For corners in CLINTON (County), Located In: T 5N R 2W, Corner Code # M-6. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

RECORDED

DEC 28 3 39 PM '98

REGISTER OF DEEDS CLINTON COUNTY MICH.

Arden S. Pierson

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, Arden S. Pierson, PS, in a field survey on SEPTEMBER 17 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: TOWNSHIP BOUNDARY SURVEY BY LUCIUS LYON IN 1826. ON EAST BOUNDARY OF SECTION 13. 40.00 SET H.M. POST - 7" HICKORY - S17°W - 13 (LINKS), (8.58') 5" ASH - N40 1/2°W - 20 (LINKS) (13.20')

CERTIFIED SURVEY BY FRED WHITE, PS #12034, DATED 11/20/97, RECORDED IN LIBER 783, PAGE 742, GIVES NO TIE TO CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND NO PHYSICAL EVIDENCE OF CORNER MONUMENTATION. SET NAIL ON TOWNSHIP LINE MIDWAY BETWEEN SECTION CORNERS, ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. REMOVED NAIL AND SET STANDARD CLINTON COUNTY MONUMENT AND MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

EAST 1/4 CORNER OF SECTION 13, T5N, R2W. STANDARD CLINTON COUNTY MONUMENT IN MONUMENT BOX.

WITNESSES NAIL & TAG #13039 IN NE SIDE POWER POLE - S33°E - 105.16' NAIL & TAG #13039 IN NE SIDE POWER POLE - S18°E - 105.86' NAIL & TAG #13039 IN SE SIDE CUT UTILITY POLE - S43°W - 31.22' SW CORNER TELEPHONE PEDESTAL - S67°E - 45.84'

FROM SOLAR OBSERVATIONS N00°06'36"W 2639.71' - M-5, DEWITT TOWNSHIP S00°13'53"E 49.75' - A-6, BATH TOWNSHIP

*STANDARD CLINTON COUNTY MONUMENT IS A 2 1/4" DIAMETER STEEL TUBE 30" LONG WITH A STAMPED BRASS CAP AND A BREAKAWAY MAGNETIC BASE.



APPROVED BY CLINTON COUNTY DEER GROUP DATED 9/23/98

Signed by Arden S. Pierson Date SEPTEMBER 21, 1998

Surveyor's Michigan License No. 13039