

**SURVEY &
REMONUMENTATION**

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners of **COMMISSION
Clinton**
(County)

Located In: Corner Code ~~##~~

1. Public Land Survey	T	<u>5N</u>	R	<u>2W</u>	M-9, <u>M-13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

MAR 15 3 37 PM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 14

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Arden S. Pierson P.S., on a field survey on October 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-9 - Original survey by Harvey Parke in 1827, recorded in Liber 1, page 169, - Found 1/2" iron with tile cylinder around at 2 ft. below road surface - 1/2" iron in monument box.

M-13 - Original survey by Harvey Parke in 1827, Recorded in Liber 2, page 362 on 2-24-80. RR spike established by Marv Fouty, P.S. and recorded in Liber 3, page 34, Ingham County records, Survey of Section 31, T5N, R1W agrees with existing point.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dewitt Township

M-9 - Found 1/2" rod in monument box - Removed 1/2" rod and placed Standard Clinton County Monument in monument box.

M-13 - Found RR spike as recorded - Accepted RR spike as correct position of corner - Set Standard Clinton County Monument in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9
(Standard Clinton County Monument in monument box)
Bath Twp. corner -South- 18.75'
MSHD tag SE side power pole -N70°E- 78.00'
MSHD tag NW side power & tel pole -S55°W- 59.57'
Face end post chain link fence -N30°W- 46.93'
N & T S. side 8"x 8" sign post -S70°E- 37.17'

M-13
(Standard Clinton County Monument in monument box)
Center pavement -West- 4.6'
N & T S. side guard rail post -S70°E- 13.55'
N & T N. side guard rail post -N62°E- 15.45'
N & T N. side 22" Cottonwood -N80°W- 52.55'
N & T SE side power pole -S27°W- 68.01'

**Standard Clinton County Monument is a 2" steel tube, 30" long with a 3/4" breakaway magnet base and stamped brass cap

Signed by Arden S. Pierson

Date November 24, 1993

Surveyor's Michigan License No. 13039

**APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 12/8/93**

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
1303 REVISED JAN. 1993

