

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Clinton

(County)

Located In:

Corner Code ##

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>5N</u> R <u>3W</u> | <u>A-9</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous                   | S _____ T _____ R _____ | _____      |
| Property in Sec.                   | S _____ T _____ R _____ | _____      |

RECORDED

Mar 15 3 38 PM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.

*Carol Woolley*

LIBER 4, PAGE 26

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**Dwight R. Schofield**

I, \_\_\_\_\_, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey December 1826 by Harvey Parke DS  
 subsequent restoration unrecorded by Mich. Dept. Transportation  
 subsequent restoration recorded by PS 18998  
 1/2" Rebar

NW	SW cor. anchor post	123.40'
NE	SE cor anchor post	67.65'
S	Centerline W. bnd. lane I-96	46.0'
N	SE cor. Sec 24	119.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rebar  
 South Centerline W. bnd. lane I-96 45.17'

Accepted monument as corner location and set Standard Clinton County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 (NW cor. Section 30)  
 Standard Clinton County Monument

South	Centerline W. bnd. lane I-96	45.17'
N	45° W Nail & Tag #34976 in 8" Pine	44.14'
N	30° E Fence anchor post	72.12'
N	10° W Nail & Tag #34976 in 8" Ash	58.34'

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 1/19/94

Date January 13, 1994

Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 34976

