

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Clinton

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>5N</u> R <u>3W</u> | <u>G-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

MAR 15 3 38 PM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 22

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Dwight R. Schofield

I, _____, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original survey December 1826 by Harvey Parke DS
 Subsequent restoration recorded by PS 12034 Liber 1, Page 337
 Subsequent restoration recorded by PS 21265 Liber 2, Page 128
 RR Spike
 N 40° E Fence post 42.08'
 S 75° W Power Pole 79.80'
 N 80° W Telephone Pole 61.00'
 West RR spike (SW cor Sec. 34, T6N, R3W, Riley) 28.43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found RR Spike over 6' of 1" Pipe
 West RR spike 28.43'
 S 75° W Nail & Tag "Consumers" in Power Pole 79.56'
 N 80° W Nail & Tag "Consumers" in Telephone Pole 61.04'

Accepted monument as corner location and set Standard Clinton County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 (NW cor. Section 3)
 Standard Clinton County Monument
 West Standard Clinton County Monument 28.43'
 S 75° W Nail & Tag "Consumers" in Power Pole 79.56'
 N 80° W Nail & Tag "Consumers" in Telephone Pole 61.04'
 N 45° E Nail & Tag "Consumers" in Telephone Pole 47.50'

Signed by *Dwight R. Schofield*
 Surveyor's Michigan License No. 3549760

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 1/13/94
8-75

Date January 13, 1994