

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in  
Clinton  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>5N</u>	R	<u>3W</u>	<u>G-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

Mar 15 3 38 PM '94

REGISTER OF DEEDS  
 CLINTON COUNTY, MICH.

*Carol Worley*

LIBER 4, PAGE 23

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**Dwight R. Schofield**

I, \_\_\_\_\_, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey December 1826 by Harvey Parke DS  
 County Surveyor calls for a  
 Stone Elm 12 N 31 1/4 E 117 & Sugar 12 N 78 W 125  
 Subsequent restoration recorded by PS 3829 Liber 1, Page 541  
 1/2" Rebar in Monument Box  
 N 45° 57' E Tag in SW side utility pole 44.05'  
 S 50° 30' E NW cor Hse #13025 118.10'  
 S 32° 31' W Center Con. power riser 51.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rebar in Monument Box  
 N 45° 57' E Tag #3829 in cut off Pole 44.13'  
 S 50° 30' E NW cor. Hse. #13025 118.10'

Accepted monument as corner location and set Standard Clinton County Monument in Monument Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 (NW cor. Section 15)  
 Standard Clinton County Monument in Monument Box  
 N 45° 57' E Tag #3829 in cut off pole 44.13'  
 S 50° 30' E NW cor. Hse. #13025 118.10'  
 N 45° W 1/2" Rebar 38.57'  
 S 45° W Consumers power pipeline riser 56.73'

APPROVED BY  
 CLINTON COUNTY PEER GROUP  
 DATED 1/19/94  
*872*

Signed by *Dwight R. Schofield* Date January 19, 1994  
 Surveyor's Michigan License No. 34976

