

HERVEY PARKE
MONUMENT

REMONUMENTATION
SECTION 12, WATERTOWN TOWNSHIP

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 9 9 03 AM '95

REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Arden S. Pierson

For corners in
Clinton COMMISSION
(County) Located In:

Corner Code #

- 1. Public Land Survey T 5N R 3W M-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

LIBER 4, PAGE 93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6		5					3		2
3										
4	7		8		9		10		11	1
5										
6	18		17		16		15		14	1
7										
8	19		20		21		22		23	2
9										
10	30		29		28		27		26	2
11										
12	31		32		33		34		35	3
13										

Arden S. Pierson P.S. In a field survey on October 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Hervey Parke DS, 1827. 80 chains set corner post to Sections 12 & 13, 22" Aspen - S20°W - 38 links; 11" Aspen - N42-1/2°W - 32 links.

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Verified 1/4" rod in monument box.
Excavated and found brick and stone at corner position. Accepted 1/4" rod as a careful and faithful perpetuation of the position of the original corner.
Set Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SE Corner Section 12
*Standard Clinton County Monument in monument box.
North 16.85' to Closing Corner
Nail & Tag #13039 in NE Side Telephone Pole - N27°W - 58.60'
Nail & Tag #13039 in SE Side Telephone Pole - N46°E - 51.18'
NE Corner House Foundation - S49°W - 109.95'
NW Corner Foundation North House Addition - S42°E - 128.62'
*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by Arden S. Pierson Date October 16, 1995

Surveyor's Michigan License No. 13039

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1978
REVISED JAN, 1983

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 10/18/95
(71-9)

9/12/95
21.2.95

LIBER 4, PAGE 94

LCRC Liber 1, Pages 301-302, by Arden Pierson, August 3, 1971, found railroad spike just below surface of bituminous, removed spike and dug down approximately 1- $\frac{1}{2}$ feet, found glass, brick along side a $\frac{3}{4}$ " pipe with $\frac{1}{4}$ " rod inside. Raised corner to surface with $\frac{1}{4}$ " copper-weld rod and set monument box. Witnesses at intersection of Airport Road and Herbison Road: 20" Maple - S70°E - 76.33'; 23" Maple - N70°E - 96.86'; NE Corner Foundation of House #13010 - S45°W - 109.87'; U.S.G.S. B.M. 1920 - S35°W - 42.98'.

Certified Boundary Survey by Fred N. White #12304 dated June 25, 1985, Liber 2, Page 847.

Certified Boundary Survey by Douglas K. Richardson #31603 dated August 16, 1988, Liber 3, Page 310.