

JAN 27 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
CLINTON COUNTY REMONUMENTATION
EAST 1/4 CORNER, SECTION 13, T5N-R3W
WATERTOWN TOWNSHIP
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Clinton</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>3W</u>	<u>M-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling In Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

RECORDED LIBER 004 PAGE 361

DEC 21 12 56 PM '99

REGISTER OF DEEDS
CLINTON COUNTY, MICH.
law
Register of Deeds Stamp
& File Number

I, Mark L. VanRaemdonck, in a field survey on June 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- Original, Lucious Lyons, D.S. 1826.
Monument: Wood post
Accessories: Cherry 9 N37°W 29
Red Oak 10 S37°W 16
- Black Leather Notebook, 7 1/2" x 9 1/2" on file in Clinton County Drain Office.
Surveyor and date unknown.
Monument: Not given.
Accessories: W. Oak 12 N65°W 48

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 12/16/99
578

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found no other record of subsequent restoration. Re-established this corner position using the single proportion method between corners M-5 and M-7. Used corner A-6, T5N-R2W, for control East and West. Found no conflicting evidence and accepted this location as the careful and faithful re-establishment of the original corner position.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set a standard Clinton County Remonumentation monument, being a 2 1/2" diameter steel tube, 30" long with a standard brass cap, stamped "P.S." 24622" and a breakaway magnetic base at the corner location described in Section B above. The monument is witnessed by the following accessories:

- N70°E 32.31' Set N&T N. face util. Pole
- S75°E 34.39' Top cen. Tele. Cable box
- S20°E 44.53' N. face sign post
- S30°W 58.65' Fnd. N&T E. face 18" Elm
- N00°02'42"E 6.72' Remon Monument at A-6
- S00°02'42"W 2633.36' Remon Monument at M-7

Bearings to A-6 and M-7 are based on solar observations.



Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date 12-16-99