

(A 13 - T5N - R2W =)

M 13 - T5N - R3W - WATERTOWN TWP. (RECORD # 86)

SURVEY & REVISION

FEB 22 1996

COMMISSION RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Clinton (County)

Located In: Corner Code #

- 1. Public Land Survey T 5N R 2W A-9, A-13
T R
T 5N R 3W M-13
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

MAR 15 3 37 PM '94

REGISTER OF DEEDS CLINTON COUNTY, MICH.

Carol Worley

LIBER 4, PAGE 16

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, Arden S. Pierson P.S. a field survey on October 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9 - Original survey by Harvey Parke, D.S., in 1827, Chas E. Hollister, County Surveyor Records stone, with iron below June, 1880 - Recorded Corner in Liber 1, page 131.- Recorded by F. White P.S. in Liber 1, page 393.

A-13 - Original survey by Harvey Parke D.S., in 1827, recorded in Liber 2, page 598 - MDOT survey notes record survey information for SE 1/4 Section 36, T5N, R3W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dewitt Township

A-9 (SW corner-Section 19) - Found 1/2" rod in monument box @ South edge of pavement -East- Accepted monumentation and placed Standard Clinton County Monument in existing monument box.

A-13 (SW corner-Section 31) - Found boatspike in monument box Verified with MDOT reference point - Excavated below and found boatspike buried 24"- Placed Standard Clinton County Monument and replaced monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 (SW corner-Section 19) (Standard Clinton County Monument in monument box)

A-13 (SW corner-Section 31) (Standard Clinton County Monument in monument box)

Watertown Twp. corner -North- 13.20'
N & T SW side power pole -N22°W- 107.73'
N & T NW side light pole -N69°E- 110.85'
N & T #25832 SE side cut off utility pole -N24°E- 102.11'
N & T #25832 SW side light pole -S35°E- 46.33'

Boatspike -North- 77.06'
PK nail S. side telephone pole -N80°W- 31.70'
N & T #16053 NW side telephone pole -N64°E- 52.83'
N & T #16053 W. side power pole -S12°E- 85.20'
N & T E. side power & telephone pole -S16°W- 154.95'

**Standard Clinton County Monument is a 2" steel tube, 30" long with a 3 1/2" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson Date November 24, 1994

Surveyor's Michigan License No. 13039

APPROVED BY CLINTON COUNTY PEER GROUP DATED 12/3/93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 12, 1975 SURVEYOR'S LICENSE NO. ARDEN S. PIERSON