

SURVEY & REMONUMENTATION

REMONUMENTATION SECTION 12, EAGLE TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JAN 17 1996

RECORDED

Nov 9 9 03 AM '95

REGISTER OF DEEDS CLINTON COUNTY, MICH. *Arden S. Pierson*

LIBER 4, PAGE 97

Register of Deeds Stamp & File Number

For corners in Clinton (County) located in: COMMISSION

Corner Code #

1. Public Land Survey	T	5N	R	4W	K-4
	T		R		
	T		R		
	T		R		
2. Property Controlling In Section	S	T	R		
	S	T	R		
3. Miscellaneous Property In Section	S	T	R		
	S	T	R		

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5		4		3		2			
3											
4	7	8		9		10		11		12	
5											
6	16	17		18		19		20		21	
7											
8	19	20		21		22		23		24	
9											
10	30	29		28		27		26		25	
11											
12	31	32		33		34		35		36	
13											

Arden S. Pierson P.S. in a field survey on September 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes survey by L. Lyon, D.S. in 1827. Set Half M. Post -- 13" Beech - S18°W - 15-1/2 links; 15" Beech - N12°E - 36 links

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod in monument box on physical centerline. Accepted 1/2" rod as a careful and faithful perpetuation of the position of the original corner.

Set Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position

West 1/4 Corner, Section 12

- *Standard Clinton County Monument in monument box
- Nail & Tag #13039 in South Side Power Pole - East - 29.88'
- Nail & Tag #13039 in South Side Power Pole - N87°W - 62.82'
- Nail & Tag in East Side 5" Walnut - N26°W - 72.14'
- Nail & Tag #13039 in East Side 30" Walnut - N09°W - 163.84'

*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by Arden S. Pierson

Date October 14, 1995

Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 10/18/95

LCRC by Larry Bryan #25832 dated January 24, 1989, dug a 3.5x3.5' hole in centerline of Wright Road 1/2 way between Northeast and Southeast corners of Section 11, found a very old 3/4" pipe 1.5' below the road surface measure North to K-3, 2649.26, measure South to K-5 2651.34' -- accepted old pipe as corner and raised to surface with a 1/2" bar and cap in monument box.

Set nail & tag #25832 North Side 14" Ash - S60°E - 66.93'
Set nail & Tag #26832 East Side 24" Maple - S20°W - 71.67'
Set nail & Tag #25832 East Side 22" Walnut - N15°W - 163.32'

Certified Boundary Survey by Larry Bryan #25832, dated January 18, 1990, Liber 4, Pages 883-884.

Found 1/2" bar in cap in monument box, over old 3/4" pipe.
Found nail & tag #25832 North Side 14" Ash - S60°E - 66.93'
Found nail & tag #25832 East Side 24" Maple - S20°W - 71.67'
Found nail & tag #25832 East Side 22" Walnut - N15°W - 163.32'

Certified Boundary Survey by Arden Pierson #13039, dated October 15, 1990, Liber 4, Pages 183-184.