

5/9/94

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in
Clinton
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>6N</u> R <u>1W</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Mar 15 3 39 PM '94
REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Carol Woolley
LIBER 4, PAGE 27
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Dwight R. Schofield

I, _____, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Harvey Parke Nov. 1826
Subsequent restoration county surveyor 1884
Subsequent restoration PS 19003 3/10/75 Liber 1, Page 911
Set 1/2" Rebar
NE Nail & Tag in 12" Oak 28.31'
SE Nail & Tag in 36" Oak 38.80'
SW Nail & Tag in 20" Willow 26.80'
WEST NW cor. Section 3, T5N, R1W, Bath 87.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rebar
NE Nail & Tag in 16" Oak 28.24'
WEST NW cor. Section 3, T5N, R1W, Bath 87.78'

Accepted monument as corner and set Standard Clinton County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 (SW corner Section 34)
Standard Clinton County Monument
N 50° E Nail & Tag in 16" Oak 28.24'
WEST Standard Clinton County Monument 87.78'
N 45° W Nail & Tag #34976 in 6" Elm 40.18'
S 55° E Nail & Tag #34976 in 48" Oak 38.49'
S 60° W Nail & Tag #34976 in 12" Maple 46.41'

Signed by *Dwight R. Schofield*
Surveyor's Michigan License No. 34976

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 1/13/94
Date January 13, 1994

