

**SURVEYOR  
REMONUMENTATION**

DEC 07 1994

RECORDED

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**COMMISSION**

For corners in

Clinton  
(County)

Located in:

Corner Code #

- |                                       |                         |            |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey                 | T <u>6N</u> R <u>1W</u> | <u>K-8</u> |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |

JAN 24 9 48 AM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Carol Woolley*

LIBER 4, PAGE 4

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Arden S. Pierson P.S. in a field survey on October 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-8 - Original survey by Harvey Parke D.S., 1826.- Chas E. Hollister, March 11, 12, & 18, 1880, Found remains of one witness established by division - Set RR iron 2½' long.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Section 23, Victor Township**

K-8 - Found RR rail section described by County Surveyor - Removed RR rail section and set Standard Clinton County Monument. (buried 8")

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 (E ¼ corner Sec.23)  
(Standard Clinton County Monument  
in monument box)

- Nail & Tag SW side power pole -N41°W- 89.60'
- Nail & Tag NW side telephone pole -S41°E- 52.80'
- Nail & Tag W. side 32" oak -S13°E- 72.35'
- Nail & Tag SE side power pole -S40°W- 151.21'

\*\*Standard Clinton County Monument is a 2" steel tube, 30" long with a 2½" breakaway magnetic base and stamped brass cap.

Signed by *Arden S. Pierson* APPROVED BY CLINTON COUNTY PEER GROUP December 2, 1993  
Surveyor's Michigan License No. 13039 DATED 12/8/93