

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

**REMONUMENTATION
SECTION 36, VICTOR TOWNSHIP**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

<u>Clinton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>1W</u>	<u>L-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

JAN 6 10 21 AM '97
REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Carrie Woolley
LIBER 4, PAGE 194
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Arden S. Pierson P.S., in a field survey on November 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ Original survey by Hervey Parke, DS, 1826. Set Half Mile Post witnessed by: W. Oak 36" - N25°E - 14 links; Hickory 6" - N67-½°W - 62 links.
- ◆ LCRC by James E. Stephens, PS, #16053 dated March 8, 1974. A ½" iron was found in the centerline of the section line road (Cutler Road) and left in position with the following witnesses:
Survey tag on the South side of a 24" Walnut tree - N48°54'E - 41.20 feet
Survey tag on the South side of a 36" Walnut tree - N61°41'E - 56.41 feet
Survey tag on the North side of 14" Walnut tree - S58°45'W - 59.65 feet

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Standard Clinton County Monument set by Dwight Schofield, PS, #34976, buried 6". Rewitnessed corner.

Distance West to the Southwest Corner of Section 36 - 2643.81'. Distance East to the Southeast Corner of Section 36 - 2643.73'.

North ¼ Corner Section 1, T5N, R1W, West - 38.84'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South ¼ Corner, Section 36

- *Standard Clinton County Monument
Nail & tag #13039 in NW side 16" Walnut - S62°W - 60.12'
Nail & tag #13039 in SW side Wood Fence Post - N18°W - 21.61'
Nail & tag #13039 in SE side Wood Fence Post - N36°E - 23.78'
Nail & tag #13039 in SE side 24" Walnut - N52°E - 41.51'

*Standard Clinton County Monument is a 2½" dia. Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson*
Surveyor's Michigan License No. 13039

Date November 16, 1996

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 11/13/96
[Signature]

LCRC by James E. Stephens, PS, dated March 8, 1974, T5N, R1W, L-1. A ½" iron rod was found in the centerline of the section line road (Cutler Road) and on a projection of a tree row South of the corner. ½" iron rod was left in position with the following witnesses:

Survey tag on the South side of a 24" Walnut tree - N68°47'E - 75.09 feet
Survey tag on the South side of a 36" Walnut tree - N73°11'E - 92.55 feet
Survey tag on the North side of a 14" Walnut tree - S21°21'W - 33.21 feet