

SURVEY & REMONUMENTATION

MAR 2 1 1996

COMMUNITY

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Victor Township

For corners in

Table with columns: Clinton (County), Located in: (Township), Corner Code #. Includes entries for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

RECORDED Dec 3 8 14 AM '96 REGISTER OF DEEDS CLINTON COUNTY, MICH. LIBER 4, PAGE 186 Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a field survey on July 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13. Contains numerical data points for survey locations.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Joseph Wampler, D.S. Monument: Wood post Accessories: Aspen 18 S69W 22 1/2 do 7 N28W 39
2.) C.E. Hollister, Field Book 5; April 21, 1902 Monument: None given Accessories: W. Oak 16 N46 1/2 W 49 Apple 4 S87E 39 1/2
3.) Jan Folkens, survey recorded L. 2, p. 503, 8/5/82 Monument: Found rerod Accessories: East 31.10' Set nail & tag in 8" Walnut N80W 31.00' Set nail & tag in fence post S20W 117.45' Set nail & tag in 24" Maple
4.) Ronnie M. Lester, survey recorded L. 2, p. 833-834, 9/30/85 Monument: Found 1/2" bar per survey recorded L. 2, p. 503 Accessories: Nail & tag in E. side 24" Oak SSW 118.14' Nail & tag in E. side 10" Elm NNW 96.56' Nail & tag in fence post WNW 31.10' Nail & tag in S. side 8" box elder WSW 66.97'
5.) Ronnie M. Lester, L.C.R.C. recorded Liber 2, p. 565, 9/30/85 Monument: 1/2" bar in centerline of road on fence West, raised with 5/8" bar Accessories: Nail & tag in E. side 24" Oak SSW 118.14' Nail & tag in E. side 10" Elm NNW 96.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 3/4" rebar as referenced in No. 3, 4, 5, 6, 7 and 8 above. Found no conflicting evidence. Accepted this location as the original corner location based on the best available evidence. Excavation to install standard monument revealed 3 steel farm implement parts at 2'+- below asphalt surface.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner: Removed 3/4" rebar and farm implement parts and installed a standard Clinton County Monument with mon box. The Monument was stamped "24622" and is witnessed by the following accessories: N50°W 37.25' Set N&T 24622 in 6" Oak S80°W 66.77' Fnd. N&T 25832 in 12" Box Elder S35°E 23.70' Set R&C #24622 in East shoulder of Meridian Rd. N60°E 22.00' Top cen. S. end CMP culv.

Signed by [Signature] Surveyor's Michigan License No. 24622

Date 11/20/96

APPROVED BY CLINTON COUNTY PEER GROUP DATED 7/17/96



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971 REVISED MAY 14, 1975 REEVAL JAN., 1983