

SEP 20 1999

SECTION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Victor Township

For corners in

Clinton (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>1W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

DEC 3 8 15 AM '96

REGISTERED DEEDS
CLINTON COUNTY MICH.

Clint Co. Victor Twp

LIBER 4, PAGE 189

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonck, in a field survey on July 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| 1.) Original
Monument: Wood post
Accessories: Tam. 4 N57W 12 1/2
do 3 S57W 21 | 4.) Maurice H. Mahieu, L.C.R.C. recorded L. 2, p. 533 11/5/84
Monument: #6 rerod
Accessories: Nail & tag in E. side 10" Elm N40W 84.55'
Nail & tag in E. side 20" Oak N25W 123.89'
Nail & tag in E. side util. pole N20E 149.78'
Nail & tag in W. side 18" Poplar N30E 98.42' |
| 2.) Hathaway J. Hanes, survey recorded L. 1, p. 472, 7/30/74
Monument: #6 reiron PK nails
Accessories: 24" Oak N35W 123.9'
10" Aspen N40E 58.50'
16" Maple S30W 172.0' | 5.) Maurice H. Mahieu, survey recorded L. 2, p. 743, 11/5/84
Monument: Found 5/8" rerod
Accessories: 10" Elm N40W 84.55'
20" Oak N25W 123.89'
util. pole N20E 149.78'
18" Poplar N30E 98.42' |
| 3.) Hathaway J. Hanes, L.C.R.C. recorded L. 1, p. 809, 9/3/74
Monument: Set #6 re-iron
Accessories: E. side 24" Oak N35W 123.9'
W. side 10" Aspen N40E 58.50'
E. side 16" Maple S30W 172.0'
PK spikes | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rerod as referenced in No. 2, 3, 4 and 5 above. Found no conflicting evidence. Excavation to install standard marker revealed no further evidence. Accepted this location as the original corner position based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Removed 5/8" rerod and replaced it with a standard Clinton County Monument and mon box. The monument is stamped "24622" and is witnessed by the following accessories:

- N15°E 50.00' Set R&C 24622 in E. shoulder
- N15°W 50.00' Set R&C 24622 in W. shoulder
- S15°E 50.00' Set R&C 24622 in E. shoulder
- S15°W 50.00' Set R&C 24622 in W. shoulder

Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date 11/17/96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983



APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 7/17/96
JFR