

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Victor Township

| Clinton (County) | Located in: | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T <u>6N</u> R <u>1W</u> | <u>M-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECORDED

Dec 3 8 15 AM '96

REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Carol Woolley

LIBER 4, PAGE 190

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a field survey on July 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Joseph Wampler 1824
Monument: Wood post
Accessories: Tam. 7 N4°W 32
B. Oak 10 S7½°E 63
- 2.) Maurice H. Mahieu, L.C.R.C. rec. L. 2, p. 534, 11/5/84
Monument: Set ½" rood (single proportion)
Accessories: Nail & tag in N. side of a util pole N80°W 20.82'
Nail & tag in S. side of a 20" Elm N55°W 100.12'
Nail & tag in N. side of a 6" Poplar S75°E 34.64'
Nail & tag in N. side of a util. pole S35°E 62.59'
- 3.) Maurice H. Mahieu, survey rec. L. 2, p. 743, 11/5/84
Monument: Set ½" rood
Accessories: Same as #2 above
- 4.) Marvin Fouty, survey rec. L. 2, p. 823, 9/11/85
Monument: Fnd. ½" bar & cap #16053
Accessories: Nail & tag NS power pole N87°W 20.95'
Nail & tag NW Poplar S80°E 34.67'
Nail & tag NS power pole S30°E 62.58'
½" bar & cap #16053 N20°W 71.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" rood as referenced in No. 2, 3 and 4 above. Found no conflicting evidence. Excavation to install standard Monument revealed no further evidence. Accepted this location at the careful and faithful re-establishment of the original corner position.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Removed ½" rood and replaced it with a standard Clinton County Monument and mon box. Monument is stamped "24622" and is witnessed by the following accessories:
N70°W 20.73' Fnd. N&T #16053 in NE face util. pole
N35°E 55.80' Top cen. N. end CMP culv.
S40°E 62.63' Fnd. N&T #16053 in N. face util. pole
N12°W 60.46' Set R&C #24622 in W. shoulder Meridian Rd.

Signed by *Mark L. VanRaemdonck*
Surveyor's Michigan License No. 24622

Date 11/17/96

STATE OF MICHIGAN
MARK L. VANRAEMDONCK
PROFESSIONAL SURVEYOR
No. 24622
LICENSED PROFESSIONAL SURVEYOR

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN 16, 1974
REVISED MAY 14, 1978
REVISED JAN., 1983

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 7/17/96
J-78