

C. SURVEY
REMONUMENTATION

DEC 07 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

COMMISSION
For corners in

JAN 24 9 46 AM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Carol Woolley

LIBER 4, PAGE 5

Register of Deeds Stamp & File Number

Clinton
(County)

Located In: Corner Code #

1. Public Land Survey T 6N R 1W M-8
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Arden S. Pierson P.S. on a field survey on October 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original surveys by Harvey Parke D.S., 1826

M-8 - John Selleck P.S. stated that County Surveyor Chas E. Hollister survey of August, 1884 & F.A. Gould survey of June 1954, confirm position of RR spike as E 1/4 post Section 24, T 6N., R 1W., Recorded in Liber 2, page 155, on 10-4-77. Recorded to update witness information in Liber 2, page 572, on 2-18-86.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 24, Victor Township

M-8 - Found RR spike - Removed RR spike and excavated - Found 1/2" iron pipe and pointed stone 0.6' SW of RR spike position - Removed pipe and placed Standard Clinton County Monument to point of stone - Set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 (E 1/4 corner)
(Standard Clinton County Monument
in monument box)

- Nail & Tag in N. side telephone pole -S64°W- 63.78'
- P.K. SW side power pole -N33°W- 53.02'
- Stephen's tag NW side tel. pole -N53°E- 41.73'
- Stephen's tag W. side tel. pole -S18°E- 82.94'

**Standard Clinton County Monument is a 2" steel tube, 30" long with a 3/2" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson Date December 2, 1993

Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 12/8/93
JFS

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

