

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Victor Township

For corners in

Clinton (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>1W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

Nov 19 10 34 AM '96

REGISTERED DEEDS
CLINTON COUNTY, MICH.

Carrie M. ...

LIBER 4, PAGE 178

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a field survey on July 26, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p>1.) Original: Joseph Wampler, D.S.
Monument: Wood post
Accessories: Elm 10 S11½°E 16
R. Oak 5 N16½°W 25½</p> <p>2.) C. Hollister, field book 1
Monument: None given
Accessories: Elm 8" S6°E 22
B. Ash 6" N49°E 6</p> <p>3.) C. Hollister, field book 3
Monument: None given
Accessories: Elm 8 S6°E 22</p> | <p>4.) Jack N. Owens, survey rec. L. 4, p. 397, 2/25/82.
Monument: Set 3/4" pipe & cap #20709
Accessories: N35°W 83.47' Set spike E. face 10" Maple
N65°W 51.50' Set spike NNE face 10" Coltonwood
N80°W 23.16' Top leaning angle iron post
N85°W 63.90' Bottom hole, S. leg traffic sign
N00°21'33"W 368.14' W 1/8 corner Sec. 32, T6N-R1E</p> |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe & cap #20709 as referenced in No 4 above Found no conflicting evidence. Accepted this position as the careful and faithful re-establishment based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set 4' section of 4" PVC sch 30 pipe over 3/4" pipe & cap filled 4" pipe with concrete and installed a standard Clinton County Monument stamped "24622" over 3/4" pipe. The standard Clinton County Monument is witnessed by the following accessories:

North on Meridian	145.00'	Set rerod & cap #24622
South on Meridian	145.00'	Set rerod & cap #24622
North on Meridian	368.14'	Fnd. rerod & cap #20709 at W 1/8 corner Sec. 32, T6N-R1E
N79°52'40"W	55.92'	Set rerod & cap #24622



Signed by Mark L. VanRaemdonck

Date 8/21/96

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 197
REVISED MAY 14, 197
REVISED JAN., 1991

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 7/17/96

JFR