

MAR 21 1997

COMMISSION

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

Victor Township

For corners in

<u>Clinton</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>1W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Nov 19 10 34 AM '96  
REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Laura Wesley*  
LIBER 4, PAGE 179  
**Register of Deeds Stamp & File Number**

I, Mark L. VanRaemdonck, in a field survey on July 26, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- Original: Joseph Wampler, D.S.  
Monument: Wood post  
Accessories: Elm 20 N18E 41  
Elm 20 S79W 89
- Hollister Book 2, June 1896  
Monument: None given, established 1/4 corner at 13 90 chains North of Southwest corner Section 32, T6N-R1E  
Accessories: Elm 30" N57 1/2 W 17 1/4

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Set standard Clinton County Monument at single proportion between M-11 and M-13. Found no evidence of Hollister's position. Found no fences or corner posts. This position is approximately 66 feet North of the centerline of the Maple River which agrees with G.L.O. topo call. Found no conflicting evidence. Accepted this position as the careful and faithful re-establishment of the corner position.

**C. Description of monument for corner and accessories to perpetuate locating the position of the corner:**

Set standard Clinton County Monument witnessed by the following accessories:  
West 28.09' Set N&T #24622 in E. face 18" Maple  
N50°W 72.18' Set N&T #24622 in N. face 24" Maple  
N10°E 105.94' Set N&T #24622 in N. face 18" Maple  
N25°E 72.17' Set N&T #24622 in W. face 25" Maple



Signed by Mark L. VanRaemdonck  
Surveyor's Michigan License No. 24622

Date 8/21/96

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 7/17/96  
J. J. J.