

SURVEY & REMONUMENTATION

FEB 02 1998

SECTION

REMONUMENTATION
SECTION 31, OLIVE TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004, PAGE 229

For corners in Clinton Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 6N R 2W B-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

RECORDED
OCT 17 9 19 AM '97
REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Carole Wootley
Register of Deeds Stamp & File Number

I, Arden S. Pierson, PS, in a field survey on July 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

◆Original Survey by Hervey Parke, DS, 1826. Set Half Mile Post, Witnessed by: Beech 20" - N59°E - 27 links; Beech 7" - N32°W - 23 links.

(No additional information from County Surveyor Notes, Recorded Surveys, or Land Corner Recordation Certificates.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set corner on Township line from proportional measurement from Section Corners, and is accepted as a careful and faithful re-establishment of the position of the original corner. Excavated a 24"x24"x18" area at corner position and found no other evidence.

Set Standard Clinton County Remonumentation Monument.

Closing Corner for T5N, R2W, is West 22.10'.

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/20/97
J.F.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South ¼ Corner of Section 31

- *Standard Clinton County Monument
- Nail & tag #13039 in South side Power Pole - N60°W - 203.07'
- Nail & tag #13039 in West side Light Pole - N10°W - 94.08'
- Nail & tag #13039 in SE side 30" Maple - N57°E - 68.19'
- Nail & tag #13039 in SE side Power Pole - N67°E - 94.28'

SW Corner of Section 31 is N89°25'24"W. 2812.65'
SE Corner of Section 31 is S89°52'36"E. 2634.84'
From solar observation.

*Standard Clinton County Monument is a 2½" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson* Date July 27, 1997
Surveyor's Michigan License No. 13039