

SURVEY & REMONUMENTATION

FEB 02 1998

**REMONUMENTATION
SECTION 31, OLIVE TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 004 PAGE 230

SECTION

For corners in Clinton (County) Located In: Corner Code #

1. Public Land Survey T 6N R 2W C-13
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
 Oct 17 9 19 AM '97
 REGISTER OF DEEDS
 CLINTON COUNTY, MICH.
Arden Pierson
 Register of Deeds Stamp & File Number

I, Arden S. Pierson, PS, in a field survey on July 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆Original survey by Hervey Parke, DS, 1826. Set post corner to Sections 31 and 32, witnessed by W. Oak 20" - N35°E - 21 links; W. Oak 26" - N32°W - 58 links.
- ◆LCRC by Arden S. Pierson, PS, #13039, dated October 1, 1979, Liber 2, Page 269. Found 3/4" iron pipe next to pointed stone. Witnessed by:
 USGS Monument - N61°W - 51.24'
 12" Walnut - S72°W - 144.01'
 Fence Post - N30°W - 33.80'

APPROVED BY
 CLINTON COUNTY PEER GROUP
 DATED 8/20/97
gfr

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe on West side pointed stone. Accepted pipe as a careful and faithful perpetuation of the position of the original corner.

4' North of physical centerline Cutler Road - 3' East of Centerline Norris Road North.

Set Standard Clinton County Monument with stone and iron placed around.

Closing corner West - 22.09'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Southeast Corner of Section 31

- *Standard Clinton County Monument and monument box
 Nail & tag #13039 in NW side Power Pole - S37°W - 134.00'
 Nail & tag #13039 in NW side 20" Walnut - S85°W - 144.39'
 Nail & tag #13039 in NE side Power Pole - N64°W - 72.58'
 Nail & tag #13039 in SE side Power Pole - N44°E - 163.20'
 To B-13, T6N, R2W, N89°52'36"W. 2634.84'
 To D-13, T6N, R2W, S89°36'01"E. 2635.93' From solar observations.
- *Standard Clinton County Monument is a 2 1/2" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by Arden S. Pierson Date July 29, 1997

Surveyor's Michigan License No. 13039