

**SURVEY &
REMONUMENTATION**

FEB 02 1998

REMONUMENTATION

SECTION 32, OLIVE TOWNSHIP

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 231

For corners in <u>Clinton</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>2W</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
Oct 17 9 19 AM '97
REGISTER OF DEEDS
CLINTON COUNTY, MICH.
Arden S. Pierson
Register of Deeds Stamp & File Number

I, Arden S. Pierson, PS, in a field survey on July 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ Original survey by Hervey Parke, DS, 1826. Set Half Mile Post, witnessed by: Beech 7" - N77°E - 23 links; Lynn 8" - N33°W - 50 links.
- ◆ Survey by Chas. E. Hollister, County Surveyor, January 28, 1890. At 40 chains from Southeast Corner Section 32, set stone for ¼ post. Witnessed by: Maple 16" - N58°E - 73½ links; Pine 7" - N41-2/3°W - 1.12 chains.
- ◆ Clinton County Surveyor Field Notes -- Witness: Sugar 8" - N55½°E - 71 links.

(OVER)

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/20/97
JSP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" rod in ¾" pipe 3' below gravel road surface in cairn of stones with brick and crockery. Accepted ½" rod in ¾" pipe as a careful and faithful re-establishment of the position of the original corner.

Replaced ½" rod in ¾" pipe with Standard Clinton County Monument.

Closing Corner for T5N, R2W, is West 23.26'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South ¼ Corner, Section 32

- *Standard Clinton County Monument and monument box
- Nail & tag #13039 in North side Power Pole - S84°W - 156.22'
- Nail & tag #13039 in East side Power Pole - N39°W - 34.30'
- Nail & tag #13039 in NW side 30" Oak - N39°E - 67.58'
- Nail & tag #13039 in SW side Power Pole - S53°E - 46.78'
- To C-13, T6N, R2W, N89°36'01"W. 2635.93'
- To E-13, T6N, R2W, S89°39'03"E. 2639.62' From solar observations.
- *Standard Clinton County Monument is a 2½" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by Arden S. Pierson Date July 29, 1997

Surveyor's Michigan License No. 13039

◆LCRC by Ronnie M. Lester, PS, #18998, dated July 31, 1972, Liber 1, Page 467. Found 1" bolt with square top in centerline of DeWitt and Cutler Roads. Measured distances North and West in close accord with original government measurement. Witnessed by:

Tag in South side 24" Pine - NW - 112.87'

#3829 Stephens Tag West side 30" Maple - NE - 67.61'

NW Corner of Brick House - SSW - 59.00'

LIBER 004 PAGE 232

◆LCRC by Arden S. Pierson, PS, #13039, dated August 29, 1977, Liber 2, Page 199. Found 1" pipe, raised with 1/2" rod. Witnessed by:

N40°W - 34.30' - Telephone Pole

N43°E - 67.58' - 26" Maple

N38°W - 101.27' - SE Corner of House

◆LCRC by Arden S. Pierson, PS, #13039, dated October 1, 1979, Liber 2, Page 269. Found 1 1/2" rod over 1" pipe. Witnessed by:

Tel. Pole - N40°W - 34.30'

26" Maple - N43°E - 67.58'

SE Corner House - N38°W - 101.27'